

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-01578-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 30-9S-18W  
1650 feet from N Section Line, 990 feet from W Section Line  
Lease Name: HILGERS Well #: 2  
County: ROOKS Total Vertical Depth: 3606 feet

Operator License No.: 31070  
Op Name: EAGLE RIVER ENERGY CORPORATIO  
Address: 7060 S. YALE #609  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3609	0	w/unknown sxs cmt
SURF	8.625	161	0	w/unknown sxs cmt

\$117.20

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/10/2006 1:00 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY COPRORA Phone: (918) 494-8928

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Tubing parted at 1215' - laid out - decided to P&A.  
Fluid at 400'. Dakota casing leak.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/10/2006 4:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran 2" tubing to 1200'. Quality Cementing pumped 130 sxs neat - cwc.  
PTOH. Squeezed with 250 sxs cement with 600# hulls.  
Max. P.S.I. 1000#. S.I.P. 200#.  
Hooked up to backside. Pumped 50 sxs 60/40 pozmix - 10% gel neat.  
Max. P.S.I. 400#. S.I.P. 200#.

Perfs:

INVOICED

DATE 8-18-06  
2007060407

RECEIVED  
AUG 17 2006  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING. RGN TANK SERVICE.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

Form CP-2/3

AUG 14 2006

RET

ANSCHUTZ DRILLING COMPANY #2 HILGERS 30-9-18W 23  
 NE SW NW

Contr. ANSCHUTZ DRILLING COMPANY ROOKS County

E 2191 RB Comm. Comp. 11-10-50 IP 156 BOPD & 6% WTR

Tops	Depth	Datum	Casing
HEEB	3328	-1137	8" 161 ACID 500: 2 BOPH/5 HR 5" 3609 <sup>1</sup> / <sub>2</sub> ACID 1000 85 BF/20 HRS, 4% WTR
TOR	3349	-1158	
LANS	3368	-1177	
ARB	3608	-1417	BAUMGARTNER POOL
T.D.	36.6	-1425	

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

