

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20114-00-00
Spot: N2S2SW Sec/Twnshp/Rge: 8-22S-33W
990 feet from S Section Line, 1320 feet from W Section Line
Lease Name: GARDEN CITY B Well #: 4
County: FINNEY Total Vertical Depth: 4850 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 12950 E. 13TH
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4380		WITH 15 SX CMT
DVT		2720		WITH 625 SX CMT
PROD	5.5	4849	0	WITH 260 SX CMT
SURF	8.625	454		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/31/2006 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (316) 636-2090

Proposed Plugging Method: CIBP @ 4380'. 1ST THOUGH TUBING AT 4350' WITH 15 SX CMT. 2ND PLUG AT 2720' WITH 25 SX CMT. 3RD PLUG AT 1550' WITH 25 SX CMT. 4TH PLUG AT 1100' CIRCULATE CMT TO 0'. 5TH PLUG USE 200 SX CMT FOR ANNULUS.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/31/2006 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CASING LEAKS AT 2994' & 1456'. CIBP @ 4380' WITH 15 SX CLASS A CMT. 2ND PLUG AT 2720' WITH 25 SX CLASS A CMT W/3% CC & 50# HULLS. 3RD PLUG AT 1550' WITH 25 SX CLASS A CMT W/3% CC & 50# HULLS. 4TH PLUG AT 1100' WITH 50 SX CLASS A CMT. 5TH PLUG AT 600' WITH 85 SX CLASS A CMT CIRCULATED TO SURFACE. TOP OFF 5 1/2" CASING WITH 5 SX CMT. HOOK UP TO 5 1/2" X 8 5/8" ANNULUS. PUMP 10 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4725	4734		
4403	4407		

INVOICED
DATE 8-23-06
2007060424

RECEIVED


AUG 21 2006

KCC WICHITA

Remarks: USED CLASS A CMT & 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed _____

Karl Jehlik
(TECHNICIAN)

Form CB-2/3

PKT