

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00483-00-00
Spot: NE Sec/Twnshp/Rge: 19-24S-34W
3960 feet from S Section Line, 1320 feet from E Section Line
Lease Name: FINNUP Well #: 1
County: FINNEY Total Vertical Depth: 2725 feet

Operator License No.: 32787
Op Name: KANSAS NATURAL GAS OPERATING, I
Address: PO BOX 818 1200 MAIN STREET
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2408		WITH 2 SX CMT
PROD	7	2720	0	
SURF	10.75	750		

\$ 88.56

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/02/2006 12:00 PM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: STEVE LEHNING Company: KANSAS NATURAL RESOURCES Phone: (620) 675-8185

Proposed Plugging Method: SET CAST IRON BRIDGE PLUG AT APPROXIMATELY 2400' INSIDE 7" CASING. USE A WIRLELINE BAILOR TO SPOT A COUPLE OF SACKS OF CEMENT ON TOP PLUG. PUMP A MUD SPACER FROM 2400' TO APPROXIMATELY 1500' FROM SURFACE WITH 30 SACKS OF CEMENT. RUN A MUD SPACER TO 1000' & PERFORATE 7" CASING WITH A COUPLE OF HOLES & CIRCULATE 7' CASING BOTH INSIDE AND OUTSIDE UP INTO 10 3/4" SURFACE PIPE. COMPLETE BY HOOKING ONTO 10 3/4" SURFACE & ATTEMPT TO PUMP INTO IT. CUT BOTH 10 3/4 & 7" CASING OFF 6' BELOW G.L. WELD CAP & BACKFILL SITE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2006 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2408' WITH 2 SX CMT. LOAD & PRESSURE TEST CASING TO 200#. PERFORATE AT 1000'. PUMP 220 SX CMT. NO BLOW ON ANNULUS. SHUT DOWN WITH 80 SX CMT OUTSIDE 7". SHUT IN PRESSURE 350#. HELD AT 300#. HOOK UP TO 7" X 10 3/4" ANNULUS. WAS FULL OF FLUID. PRESSURED IMMEDIATELY TO 200# WITH 2 SX CMT. HELD AT 100#. DID NOT WANT TO GO TO HIGHER PRESSURE DUE TO HOMEMADE HEAD.

Perfs:


Top	Bot	Thru	Comments
2552	2592		
2502	2522		
2456	2478		
2434	2452		

NOTICED
DATE 8-23-06
2007060425
RECEIVED
AUG 21 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON.

Plugged through: CSG

District: 01



Signed Ken Jehlik
(TECHNICIAN)

Form CP-23

PET