

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21548-00-00
Spot: E2SENV Sec/Twnshp/Rge: 8-26S-3E
3699 feet from S Section Line, 3078 feet from E Section Line
Lease Name: HOOVER Well #: 1
County: BUTLER Total Vertical Depth: 2817 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2814		
SURF	8.625	206		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/16/2006 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DAVE WERTZ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2006 6:20 PM KCC Agent: DAVE WERTZ

Actual Plugging Report:

Dug out head. A 3' piece of 4-1/2" in a head was setting on 8-5/8". 4-1/2" inside of 8-5/8" down 4'. Cut off 8-5/8" and welded a slip on collar to the 4-1/2". While taking the stretch on the 4-1/2", it parted at 60'. Ran 1" to 250' outside of 4-1/2". Circulated cement to surface. Pulled 1" and ran 1" inside of 4-1/2". Circulated cement to surface.

60/40 posmix with 3% gel

United Cement #7086

Perfs:

RECEIVED
KCC DISTRICT #2
AUG 2 1 2006
WICHITA, KS

Remarks: CONTROL #2006-0053-001

Plugged through: TBG

RECEIVED
AUG 2 3 2006
KCC WICHITA

District: 02

Signed David Wertz
(TECHNICIAN)

PPT