

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22587-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 32-13S-14W  
2970 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: MILLER F Well #: 7  
County: RUSSELL Total Vertical Depth: 3308 feet

Operator License No.: 32322  
Op Name: DENIS F. ROBERTS  
Address: BOX 1252 3904 FAIRWAY DR.  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	2.5	0		7 SX
PROD	5	3302	0	150 SX
SURF	8	390	0	250 SX

*\$107.51*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/17/2006 9:00 AM  
Plug Co. License No.: 33695 Plug Co. Name: MID-KAN WELL SERVICE, LLC  
Proposal Rcvd. from: ARNIE MCCALIS Company: MID-KAN WELL SERVICE, LLC Phone: (785) 483-4400

Proposed  
Plugging  
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/17/2006 2:45 PM KCC Agent: CASE MORRIS

**Actual Plugging Report:**

**Perfs:**

Ran tubing to 3000'.  
Pumped 120 sxs 60/40 pozmix - 10% gel cement with 300# hulls.  
Pulled to 1500'.  
Circulated with 100 sxs cement with 400# hulls.  
POOH. Pumped 30 sxs cement down casing.  
Max. P.S.I. 1000#. S.I.P. 600#.  
Backside was full of cement.

INVOICED  
DATE 8-23-06  
2007060420

RECEIVED  
AUG 22 2006  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

*AV*

Signed \_\_\_\_\_

*Case Morris*  
(TECHNICIAN)

AUG 18 2006


*ACT*

CITIES SERVICE OIL &  
 GAS CORPORATION 32-1  
 800 SUTTON PLACE #7 'F' MILLER SE SV  
 WICHITA, KS 67202

CONTR: DUKE DRILLING CO. #3 CTY RUSSELL

GEOL ROGER BOEKEN FIELD GORHAM

ELV 1871 KB SPD 4/25/85 CARD ISSUED 8/8/85 IP P 14 BO & 706 BWF  
 1863 GL ARB OH 3302-3308



LOG	Tops	Depth/Datum
TOP	.....	2756-885
HEEB	.....	2984-1113
TOR	.....	3001-1130
LANS	.....	3037-1166
BKC	.....	3270-1399
ARB	.....	3307-1436
RTD	.....	3308-1437

API 15-167-22,587  
 8 5/8 " 500+, 5 1/2 " 3302 / 150SX  
 NO CORES OR DSTS  
 MICT - CO, (ARB OH), AC 100G (15%), SWB DVA  
 POP, P 7 BO & 48 BWPD, (5/28/85), OFF PMP, AC  
 POP, P TR OIL & 19 BW / 24 HRS, OFF PMP, RE-AC  
 POP, P 14 BO & 706 BW / 24 HRS, (7/10/85)

, NAT,  
 (15%),  
 (15%),