

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22367-00-01
Spot: ^{FZ} SWSWNE Sec/Twnshp/Rge: 21-14S-16W
2970 feet from S Section Line, 2180 feet from E Section Line
Lease Name: DREILING A Well #: 7
County: ELLIS Total Vertical Depth: 3408 feet

Operator License No.: 4787
Op Name: DENNING, TOM DBA T. D. I. OIL OPER
Address: 1310 BISON RD.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		994		325 SX
PROD	4.5	3394	0	125 SX
SURF	8.625	162	0	130 SX

\$ 110.76

Well Type: EOR UIC Docket No: E27898.1 Date/Time to Plug: 08/17/2006 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DEAN IVES Company: TDI OIL OPERATIONS Phone: (785) 628-2593

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV at 994' w/325 sxs.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2006 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 200 sxs cement with 500# hulls.
Max. P.S.I. 500#. S.I.P. 300#.
Hooked up to the annulus. Instant 1000#.

Perfs:

Top	Bot	Thru	Comments
3358	3362		
3182	3191		
3144	3148		
3122	3126		

INVOICED


DATE 8-23-06
200 7060421

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

RECEIVED

AUG 22 2006

KCC WICHITA

Form CP-2/3

AUG 18 2006

Plg

TDI OIL OPERATIONS
HAYS KS 67601

21-14S-16W
130' E, C SW SW NE

#7 DREILING A OWWO

site 1-3/4 S & 2 E OF VICTORIA KS
contr: UNKNOWN
geol: NONE

cty: ELLIS
field: DREILING

API 15-051-22367

date 10/01/2001 spc date 08/21/2001 orig comp 08/21/2001 card issued 10/01/2001 last revised 10/01/2001

	Y	

ELV 1865 KB, 1860 GL LOG

tops.....	depth/datum
ANH.....	966 +899
TOP.....	2850 -985
HEEB.....	3068 -1203
TOR.....	3087 -1222
LANS.....	3114 -1249
PBTD.....	3170 -1305
BKC.....	3354 -1489
CONG.....	3368 -1503
ARB.....	3388 -1523
LTD OLD.....	3407 -1542
RTD OLD.....	3408 -1543

IP status
INJ, LKC 3122-3148 OA, 08/28/2001
OLD INFO: OPERATOR WAS D OIL, 7 DREILING A, SPD
04/15/1981, 04/21/1981 8 5/8" 862 / 130 SX, 4 1/2" 3394 / 450
SX, OIL, P 17 BOPD & TR WTR, LKC 3283-3305 OA, ARB
3394-3408 , 07/01/1981(CARD ISSUED 07/09/1981)
CONTR: DREILING OIL
NO CORES
DST (1) 3343-3392 (PENN CONG), / 30-30-20-0, REC 20' M,
REMARK: NO FSIP ISIP 128# IFP 64# -64# FFP 64# -73#
DST (2) 3392-3408 (ARB), / 30-30-30-30, REC 45' HOVM, 185'
OCM, 60' OCMW ISIP 1091# FSIP 1091# IFP 64# -109# FFP
137# -164# BHT 100'

COPYRIGHT 2001
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)