

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20149-00-00

Spot: NWNWSE

Sec/Twnshp/Rge: 25-15S-27W

2310 feet from S Section Line,

2310 feet from E Section Line

Lease Name: WHITNEY

Well #: 1

County: GOVE

Total Vertical Depth: 4379 feet

Operator License No.: 3230

Op Name: FROELICH, MORRIS DBA FROELICH OI

Address: PO BOX 218

GORHAM, KS 67640

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	5.5	4361	0	w/unknown sxs cmt
------	-----	------	---	-------------------

SURF	8.625	254	0	w/175 sxs cmt
------	-------	-----	---	---------------

\$142.32

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/18/2006 10:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: MORRIS FROELICH

Company: FROELICH OIL

Phone: (785) 637-5460

Proposed Plugging Method: Ordered 380 sxs 60/40 pozmix - 10% gel - 600# hulls.

Dakota 598'-898'. Anhy.1943'-1987'.

CIBP set - over miss perfs. LKC zones open.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/18/2006 11:10 AM

KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Rigged to 8 5/8" casing - pumped 5 sxs 60/40 pozmix with 600# P.I.P.

No shut in pressure - blew small hole below nipple at top of head.

Rigged to 5 1/2" casing - pumped 375 sxs 60/40 pozmix with 600# hulls mixed in to pressure.

Max. P.S.I. 500#. S.I.P. 150#.

INVOICED
DATE 8/24/06
INV. NO. 2007060440

Remarks: QUALITY WELL SERVICE-TICKET #21002.

Plugged through: CSG

RECEIVED
AUG 23 2006
KCC WICHITA

District: 04

Signed

(TECHNICIAN)

Form CP-2/3

AUG 21 2006

PCT

AL WHITNEY

25-15-2
NW NW S

GOVE

FIELD WHITNEY DISC.

P 126.28 BOPD + 10%
WTR/MISS 4361-4379
GR 35.5

DATE	TIME	DEPTH	TEMP	WTR	MISS	GR
5/5/5	254/175SX	5 1/2"	4361			
DST. 1	3958-4020(KC)	/30-30-30-30,				
BHP	370-370#	, FP 40-52#				
DST. 2	4019-4050(KC)	/30-30-60-30,				
GIP	210'OIL, 200'MO, 40'OCWM,					
	1335-1275#	, FP 48-178#				
DST. 3	4050-4100(KC)	/30-30-90-30,				
GIP	60'VSOCM, 150'MW, W/SP O					
BHP	1255-1135#	, FP 35-95#				
DST. 4	4342-78(MISS)	/30-30-90-60,				
NO	BHP 1180-1180#	, FP 40-205#				
MICT	DRLG CEM, SD/14HRS	, FU 400' O				
SD/14HRS	FU 500'OIL + SOME MUD, A					
SWB LD	SWB 5.01 BO/1ST HR, 4.18BO					
HR	4.18 BO 3RD HR, SD/12HRS	, FU 1'				
OIL	SWB DWN SWB AVG 5.49 BOPH/7HRS					
1110'	OIL SWB DWN A1000 REC LD, SWB					

(OVER)

WIRE LOGGING SERVICE
W. C. H. H. H. H. H.