

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22494-00-00

Spot: NENWNW

Sec/Twnshp/Rge: 10-7S-20W

4950 feet from S Section Line,

4290 feet from E Section Line

Lease Name: PROBASCO A

Well #: 3

County: ROOKS

Total Vertical Depth: 3575 feet

Operator License No.: 5011 •

Op Name: VIKING RESOURCES, INC

Address: 105 S BROADWAY, STE 730
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|------------|
| PROD | 4.5 | 3560 | | 550/200 SX |
| SURF | 8.625 | 208 | | 160 SX |

\$ 116.19

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/19/2006 1:00 PM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: HAROLD BELERIEVE

Company: VIKING RESOURCES, INC.

Phone: (785) 483-3144

Proposed
Plugging
Method:

Order 225 sxs 60/40 pozmix - 10% gel with hulls.

Plugging Proposal Received By: HERB DEINES

WitnessType: NONE

Date/Time Plugging Completed: 08/19/2006 2:30 PM

KCC Agent: HERB DEINES

Actual Plugging Report:

8 5/8" to 208' w/160 sxs cement.
4 1/2" to 3560' w/200 sxs cement.
DV 1697' w/550 sxs cement.
Deep casing leak.
Tied onto production casing and pumped 192 sxs cement with 800# hulls.
Max. P.S.I. 1100#. S.I.P. 900#.
Annulus full of cement with instant pressure of 500#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3475 | 3482 | | |
| 3462 | 3468 | | |

INVOICED
DATE 8/24/06
NO. 2007060443

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

RECEIVED

Form CP-2/3

AUG 23 2006

KCC WICHITA

AUG 21 2006

PIA

