

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL-PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

-Form CP-1  
September 2003  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

API # 15 - 113-21171-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 1-25-86

Well Operator: K & S Oil (Owner / Company Name) KCC License #: 32381 (Operator's)

Address: 1520 N Grimes City: McPherson

State: Kansas Zip Code: 67460 Contact Phone: ( 620 ) 241 - 4901

Lease: George White Well #: 1 Sec. 24 Twp. 18 S. R. 1  East  West

SE - SW - NW - Spot Location / QQQQ County: MP McPherson

3070 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

4382 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 218 Cemented with: 150 Sacks

Production Casing Size: 5 1/2 Set at: 2889 Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2834-2835' Cast Iron Bridgeplug set at 2450' Perforated 2350-2354'

Elevation: 1514 ( G.L. /  K.B.) T.D.: 2890' PBTD: \_\_\_\_\_ Anhydrite Depth: \_\_\_\_\_

Condition of Well:  Good  Poor  Casing Leak  Junk in-Hole (Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand off perms to 2300' and bail in 5 sacks cement on top of sand bridge. Rip casing at 2250' and pull out. Build bridge at 250' and fill with cement.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: Jay Krehbiel

Phone: ( 620 ) 241 - 4901

Address: 1520 N Grimes City / State: McPherson, KS 67460

Plugging Contractor: Mike Kelso (Company Name) KCC License #: 31528 31529

Address: P. O. Box 467 Chase, KS 67524-0467 Phone: ( 620 ) 938 - 2943 (Contractor's)

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8-13-06 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**RECEIVED  
AUG 17 2006  
KCC WICHITA**

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

August 21, 2006

K & S OIL  
1520 N. GRIMES  
WICHITA, KANSAS 67460

Re: WHITE GEORGE #1  
API 15-113-21171-00-00  
SESWNW 24-18S-1W, 3070 FSL 4382 FEL  
MCPHERSON COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000