

RECEIVED  
AUG 07 2006  
KCC WICHITA

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15-195-00723 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_.

Well Operator: Gore Oil Company KCC License #: 5552  
(Owner/Company Name) (Operator's)

Address: P.O. Box 2757 City: Wichita

State: KS Zip Code: 67201-2757 Contact Phone: ( 316 ) 263 - 3535

Lease: Hedstrom Well #: 3 Sec. 3 Twp. 11 S. R. 21  East  West

S/2 - NE - - - - Spot Location / QQQQ County: Trego

3300 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" Set at: 221' Cemented with: 135 Sacks

Production Casing Size: 5 1/2" Set at: 3661' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perf 3661-3668'

Elevation: 2096' ( G.L. /  K.B.) T.D.: 3668' PBDT: \_\_\_\_\_ Anhydrite Depth: 1539'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): As per KCC Agent's instructions.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Lenny Dinkel

Phone: ( 308 ) 345 - 1597

Address: 202 Karrer Street City / State: McCook, NE 69001

Plugging Contractor: Swift Services, LLC Company Tools KCC License #: 32382 99998  
(Company Name) (Contractor's)

Address: P.O. Box 466, Ness City, KS 67560-0466 Phone: ( 785 ) 798 - 2300

Proposed Date and Hour of Plugging (if known?): 8/2/06 - 2:00pm

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8-2-06 Authorized Operator / Agent: Larry M. Jack  
(Signature)

\*Well already plugged KCC-DG  
Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

*Log Bureau  
Dec 19, 1955*

Drilled for Harry Gore-Herman Geo. Kaiser Farm Hedstrom No. 3 Depth 3668'  
 Contractor Veeder Supply & Dev'l. Co. Pipe 3661' 5 1/2" csg. cemented w/100 sacks cement  
 Location NE/4 Sec. 3 Twp. 11 Range 21  
 Commenced 11-10-1955 Completed 11-23-1955 County Trego State Kansas

Soil	0	221	221	TOPS:	
Shale and shells	221	505	284	Topeka	3116
Shale and sand	505	645	140	Heebner	3323
Sand	645	795	150	Toronto	3341
Shale and sand streaks	795	1230	435	Lansing KC	3362
Shale and shells	1230	1539	309	Base KC	3591
Anhydrite	1539	1580	41	Simpson Dol.	3654
Shale and shells	1580	2160	580	Arbuckle	3660
Lime and shale	2160	3285	1125		
Lime	3285	3660	375		
Arbuckle	3660	3668	8		
T. D.	3668				

*2096 KB  
Potential: 344*

RECEIVED  
AUG 07 2006  
KCC WICHITA

AFFIDAVIT

STATE OF KANSAS )  
Montgomery County) SS

Leo C. Veeder, of lawful age, being first duly sworn on oath, deposes and says:

THAT he is a resident of Cherryvale, Montgomery County, Kansas; that he knows and hereby on oath states that the above drilling log covering the Hedstrom #3 well located in Section 3-11-21, Trego County, Kansas, is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.  
By: Leo C. Veeder  
Leo C. Veeder

Subscribed and sworn to before me this 26th day of November, 1955.

Leo Lawson  
Notary Public

My commission expires July 11, 1956.