

RECEIVED
AUG 08 2006
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-051-20089-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date Spud 7/18/67

Well Operator: Petroleum Management, Inc. KCC License #: 5242
(Owner / Company Name) (Operator's)

Address: 14201 E. Central Wichita, KS 67230 City: Wichita

State: Kansas Zip Code: 67230 Contact Phone: (316) 733-5600

Lease: Leiker C Well #: 2 Sec. 17 Twp. 15 S. R. 17 East West

- NW - SW - NW Spot Location / QQQQ County: Ellis

3630 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

4950 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # E-15655 Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: 225 Sacks

Surface Casing Size: 8.625 Set at: 1123 Cemented with: 225 Sacks

Production Casing Size: 4.5 Set at: 3562 Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: Open hole 3562'-3568'; BP @ 3552'; Perfs 3440'-3442', 3422'-3424', 3402'-3405', 3352'-3356', 3339'-3342'; packer and parted tubing @ 3156'.

Elevation: 1972 (G.L. / K.B.) T.D.: 3568' PBDT: 3156' Anhydrite Depth: 119
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Shoot off casing @ 1905'; pull to 1775' spot 80 sx plug; pull to 1175' spot 35 sx plug; pull to 525' spot 35 sx plug; pull to 150' circulate cement to surface w/ 50 sx.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? No ACO-1 in 1967.

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Gary L. Reed, Consulting Engineer Phone: (316) 733-4798

Address: 14200 Brookline Ct. City / State: Wichita, KS 67230

Plugging Contractor: Express Well Service KCC License #: 6426
(Company Name) (Contractor's)

Address: P.O. Box 19, Victoria, KS 67671-0019 Phone: (785) 735-9405

Proposed Date and Hour of Plugging (if known?): 8/3/06 - 4:00pm

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/4/06 Authorized Operator / Agent: Gary L. Reed, as Agent
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

* Well plugged - KCC-DIG