

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-20856-00-01
Spot: S2NWSENE Sec/Twnshp/Rge: 15-12S-28W
3465 feet from S Section Line, 990 feet from E Section Line
Lease Name: SELENSKY Well #: 1-15
County: GOVE Total Vertical Depth: 4546 feet

Operator License No.: 7311
Op Name: SHAKESPEARE OIL CO., INC.
Address: 202 WEST MAIN ST.
SALEM, IL 62881

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1230	0	w/525 sxs cmt

\$ 147.75

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/26/2006 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TOM LARSON Company: SHAKESPEARE OIL COMPANY Phone: (620) 653-7368

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix and 6% gel.
Plug through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2006 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

8 5/8" surface casing set at 1230'. Well was re-entered on 07/12//2006.
Formerly known as Gove 15-1. Plugged as D&A on 12/13/1984.
Drilled to 2149'. Bit outside of wellbore.
Ran drill pipe to 2140' - pumped 25 sxs cement - displaced with heavy drilling mud.
Pulled drill pipe to 1295' - pumped 100 sxs cement.
Pulled drill pipe to 191'. Loaded hole with drilling mud. Pumped 35 sxs cement. Cement to surface.

INVOICED
DATE 8-17-06
2007 060405

RECEIVED
AUG 16 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #25929.

Plugged through: DP

District: 04

100

Signed

Darrel Dipman

(TECHNICIAN)

Form CP-2/3

JUL 27 2006

PKT

IREX OPERATING COMPANY
 1331 17TH ST. #800
 DENVER, CO 80202

REPLACEMENT CARD
 #15-1 GOVE
 15-12-20W
 C 3/2 NW 51 14

COUNTY AGERCROMBIE BEILLING CITY GOVE
 GEOL RICK HALL FIELD WC

SLV 2725 KB SPD 12/3/84 CARD ISSUED 2/28/85 IP D&A/MISS
 2720 GL DRLG COMP 12/11/84 12/13/84
 API 15-063-20,856

LOG	Tops	Depth/Datum
HEEB SH		3651-1126
LANS		3890-1165
BKC		4169-1444
PAW		4312-1587
MISS		4506-1781
RTD		4546-1821

R 5:8 " 1229.97/525SX
 DST (1) 4069-90 (LKC J) / 15-30-15-45, REC 3' DM
 SPKS OIL, SIP 67-67#, FP 67-67 / 67-67#, HP 2090-2090
 DST (2) 4100-28 (LKC) / 15-30 30-60, 250' GIP, REC 50'
 (55% OIL, 45% M), SIP 1000-1218#, FP 67-67 / 67-67
 2090-2090#

INFO RELEASED: 3/14/85 - WAS D&A - TIGHT HOLE
 NOTE CORRECTION: 12/13/84 - DUPLICATE FILING -
 DAILY FIRST REPORTED IN SW SE NE, API 15-063-20,825