

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20456-00-00
Spot: NESESWNE Sec/Twnshp/Rge: 8-5S-24W
2080 feet from N Section Line, 1520 feet from E Section Line
Lease Name: WYRILL Well #: 2
County: NORTON Total Vertical Depth: 3940 feet

Operator License No.: 33268
Op Name: RL INVESTMENT, LLC
Address: 217 SAINT PETER ST.
MORLAND, KS 67650

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	220		

\$128.05

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/10/2006 2:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: CHUCK RHOADES Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Order 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 08/10/2006 2:00 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2075' w/25 sxs.
2nd. Plug at 1225' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

INVOICED
DATE 8-17-06
2007060404

RECEIVED
AUG 16 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

AUG 15 2006

PCT