

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20378-00-00  
Spot: SWSENW Sec/Twnshp/Rge: 12-11S-25W  
2970 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: TIDBALL Well #: 4  
County: TREGO Total Vertical Depth: 3963 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment	
PROD	4.5	3959	0	w/175 sxs cmt	\$ 128.80
SURF	8.625	213	0	w/175 sxs cmt	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/01/2006 10:00 AM  
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.  
Proposal Rcvd. from: DAN WEINHOLD Company: GLM COMPANY Phone: (785) 483-1599

Proposed Plugging Method: Ordered 350 sxs cement and 500# hulls.  
Re-ordered 150 more sxs cement.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/01/2006 4:00 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 3920' - spotted 100 sxs cement with 250# hulls.  
Pulled tubing to 3000' - spotted 100 sxs cement with 250# hulls.  
Pulled tubing to 1500' - circulated with 100 sxs cement.  
Pulled all tubing and squeezed with 110 sxs cement.  
Max. P.S.I. 250#. S.I.P. 250#.  
Tied to 8 5/8" x 4 1/2" annulus and squeezed 50 sxs cement.  
Max. P.S.I. 400#. S.I.P. 400#.  
Total of 460 sxs 60/40 pozmix - 10% gel and 500# hulls.

Perfs:

INVOICE  
DATE  
100.00

RECEIVED  
AUG 16 2006  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

*M*

Signed

*Roger Moses*

(TECHNICIAN)

AUG 07 2006

*PET*

