

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22079-00-00
Spot: SWSE Sec/Twnshp/Rge: 22-15S-25W
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: CARUSO Well #: 2
County: TREGO Total Vertical Depth: 4480 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------------|
| L1 | 4 | 4416 | | 200 SX |
| PROD | 5.5 | 4489 | 0 | w/525 sxs cmt |
| SURF | 8.625 | 213 | 0 | w/145 sxs cmt |

\$ 145.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2006 11:00 AM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel - 23 sxs gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2006 12:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Swift Services rigged to 5 1/2" casing with a swedge - pumped 50 sxs 60/40 pozmix with 300# hulls mixed in, followed with 23 sxs gel with 300# hulls mixed in, followed with 130 sxs 60/40 pozmix - pumped to pressure.
Max. P.S.I. 1700#. S.I.P. 1700#.
Rigged to 8 5/8" casing - pumped 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4410 | 4418 | | |

INVOICED
DATE 8-17-06
2007060400


RECEIVED
AUG 16 2006
KCC WICHITA

Remarks: SWIFT SERVICES, INC. TICKET #10570.

Plugged through: CSG

District: 04

Signed _____



(TECHNICIAN)

AUG 11 2006

PKT

STATE: KANSAS COUNTY: TREGO
 FIELD: GOOD SCIENCE FLD(MISS) 22-15S-25W
 OPER: HESS OIL C SW SE
 WELL: 2 CARUSO 660 FSL 1980 FEL SEC
 API: 15-195-22079 ELEV: 2447 KB
 SPUD: 02/02/91 COMP: 04/09/91 2439 GR
 DTD: 4480 LTD: FTD: MISSISSIPPIAN PBDT:

LOC: 20 MI S/SE COLLER, KS

IP: COMP 4/9/91, IPP 5 BOPD, 48 BWPD, GTY 41 PROD ZONE- MISS 4410-4418
 NO CORES, ONE DSTS

LOG TOPS:

| | | | |
|-----------------|------------|------------------|------------|
| ANHYDRITE | 1888 559 | MARMATON | 4150 -1703 |
| HEEBNER | 3766 -1319 | PAWNEE | 4227 -1780 |
| LANSING | 3808 -1361 | FORT SCOTT | 4304 -1857 |
| STARK SH | 4036 -1589 | MISSISSIPPIAN LS | 4401 -1954 |
| BSE KANSAS CITY | 4100 -1653 | MISSISSIPPIAN DO | 4408 -1961 |
| TD | 4480 -2033 | | |

LOG TYPES: GRDL:

CSGS: 8 5/8 @ 213 W/145 SX, 5 1/2 @ 4480 W/525 SX; LNR: 4 @ 4246-4416 W/200 SX,
 TBG: 2 3/8 @ 4390, DRLG COMP 02/10/91 RIG REL 02/10/91

DSTS: DST # 1 (CHEROKEE MISSISSIPPIAN) 4320-4430, OP 45 MIN, SI 45 MIN,

OP 1 HR, SI 45 MIN, REC: 124 FT SOCM, 248 FT OCM, 248 FT OIL, 124 FT SOCMW, IFP 160,
 FFP 277, IFP 330, FFP 372, ISIP 1061, FSIP 1061, IHP 2247, FHP 2226, BHT 132;

PERFS: PERF (MISSISSIPPIAN) 4410-4418 W/1 PF, ACID W/500 GALS, NEFE ,
 PRODUCING INTERVAL: PERF (MISSISSIPPIAN) 4410-4418,

OPER ADD: BOX 1009, MCPHERSON, KS, 67460 PHONE (316) 241-4640;

CONTR: MALLARD J V

GEOL: BETH FUHR

WELL ID CHANGES: ELEV CHGD FROM 2380 GR;