

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21939-00-00
Spot: NENWNWNW Sec/Twnshp/Rge: 26-15S-25W
5280 feet from S Section Line, 4730 feet from E Section Line
Lease Name: GIESS-FRYE Well #: 1
County: TREGO Total Vertical Depth: 4464 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment	
PROD	5.5	4453	0	275 SX	\$ 145.08
SURF	8.625	203	0	140 SX	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2006 1:00 PM
Plug Co. License No.: 5663 Plug Co. Name: HESS OIL COMPANY
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix -10% gel - 23 sxs gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2006 2:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Swift Services rigged to 5 1/2" casing with a swedge - pumped 50 sxs 60/40 pozmix with 300# hulls mixed in, followed with 22 sxs gel and 300# hulls, followed with 145 sxs 60/40 pozmix. Max. P.S.I. 1000#. S.I.P. 0#.
Hole has slow seep. Well may need to be topped off.
Rigged to 8 5/8" casing - pumped 10 sxs cement with 300# P.I.P.
Blew small hole in 2" nipple - backside full of cement.

Perfs:

Top	Bot	Thru	Comments
4453	4464		

INVOICED
DATE 8-17-06
2007060400
RECEIVED
AUG 16 2006
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET#10570.

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

AUG 11 2006

PKT

replacement card

HESS OIL COMPANY
MCPHERSON, KS 67460

26-15 -25W
5280'FSL & 4730'FEL, SEC

#1 GIESS-FRYE

site: 6 N & 1-3/4 W OF ARNOLD, KS	city: TREGO	API 15-195-21939
contr: MALLARD DRILLING, INC	held: GOOD SCIENCE	
geol: JAMES C. HESS		
lr date 10/05/87	spd date 10/17/87	drig comp 10/23/87
	card issued 12/16/87	last revised 05/10/89

ELV: 2488 KB LOG
tops.....depth/datum
*ANH1918 +570
*B/ANH.....1956 +532
HEEB.....3808 -1320
*TOR.....3826 -1338
LANS.....3849 -1361
STARK.....4080 -1592
*BKC4134 -1646
MARM.....4149 -1661
PAW.....4266 -1778
FT SC.....4346 -1858
*CHER SH.....4370 -1882
*MISS LM.....4439 -1951

IP status:
OIL, P 40 BO & 70 BWPD, MISS 4453-4464,
MISS DOL4453 -1965
RTD.....4464 -1976
*SAMPLE TOP
CORRECTION: 5/10/89 - CORRECTED FLD NAME
NOTE: CORRECTION: 1/20/88 - ORIG FR AS 5280'FSL &
4730'FWL, SEC
CSG: 8-5/8" 203 / 140 SX, 5-1/2" 4453 / 275 SX
NO CORES
DST (1) 4424-4464 (MISS), / 30-45-30-45, REC 105'
HOCM (70% M, 30% OIL), 120' HO & GCM (50% OIL,
40% OIL, 10% G), 180' VHO & GCM (10% M, 60% OIL,
30% G) ISIP 1130# FSIP 1087# IFP 86# -129# FFP
183# -194# IHP 2297# FHP 2253# BHT 120 °

COPYRIGHT 1988

MICT - CO, (MISS OH), AC 3000 GAL, GSO, SET 2" TBG AT 4458, POP, P 40 BO & 70 BWPD (GR 38), 10/29/87