

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-20069-00-02
Spot: NWNESW Sec/Twnshp/Rge: 35-8S-29W
2300 feet from S Section Line, 3630 feet from E Section Line
Lease Name: PRATT Well #: 2
County: SHERIDAN Total Vertical Depth: 4225 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment	
L1	2.875	2085		CWC	\$137.31
PROD	4.5	4224	0	w/200 sxs cmt	
SURF	8.625	221	0	w/180 sxs cmt	

Well Type: SWD UIC Docket No: D24068.0 Date/Time to Plug: 07/26/2006 11:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 340-2773

Proposed Plugging Method: Ordered 100 sxs Midcon II cement and 200# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2006 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 221' w/180 sxs.
4 1/2" production casing set at 4224' w/200 sxs.
DV Tool at 2450' w/635 sxs. PBTD 3410'.
Ran tubing to 1980' - pumped 35 sxs cement with 0# hulls. Cement to surface.
Pulled tubing to surface. Connected to 2 7/8" production casing - pumped 15 sxs cement.
Max. P.S.I. 250#. S.I.P. 100#.
Connected to 8 5/8" surface pipe - pumped 1/2 sx cement.
Max. P.S.I. 500#. S.I.P. 500#.
Connected to 4 1/2" production casing - pumped 1/2 sx cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
2105	2155		

INVOICED
DATE 8-17-06
NO. 2007060398

Remarks: SWIFT SERVICES, INC. #10468.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

JUL 27 2006

PKT

ROCK ISLAND OIL & REF. CO., INC. #2 PRATT

35-11-29W
NW NE SW

Contr. RED TIGER DRLG Cty. SHERIDAN

Geol. Pool HOXIE WEST

E. 2819 KB Cm. 1/25/68 Cp. 3/14/68 IP P. 103 BOPD, NW
LANS 3998-4108

API 15-179-20,069

LOG Tops	Depth	Datum	Csg.
			8" 221/180 SX, 4" 4224
			DST 3556-92/1', 75' MD, BHP 1001
			897#/30", FP 63-68#
ANHY	2436	+ 383	DST 3660-84/75", 10' MD, BHP 349
B/ANHY	2474	+ 345	344#/30", FP 42-52#
HEEB	3841	-1022	DST 3816-64/2HRS, 60' GIP, 1090'
TOR	3912	-1093	SW O/S, 30' SOCM, BHP 1239
LANS	3926	-1107	1233#/30", FP 52-549#
BKC	4156	-1337	DST 3898-3922/1', WB, 3' MD O/S
			BHP 26-26#/30", FP 26-26#
RTD	4224	-1405	DST 4053-4102/2 HRS, 75' MD, BHP
			1254-1120#, FP 52-63#
			DST 4075-4125/70, 90' MD, BHP 248-
			148#/30", FP 63-84#
			PF 3998-4002, 4054-58, 4104-08, A
			2500, SWB 10 BOPH, /6 HRS, POP.

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS