

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-21398-00-01
Spot: S2NESW Sec/Twnshp/Rge: 29-9S-22W
1650 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BRASSFIELD Well #: 3
County: GRAHAM Total Vertical Depth: 3875 feet

Operator License No.: 5430
Op Name: ENERGY THREE, INC.
Address: 1437 OLD SQUARE RD #201A
JACKSON, MS 39211

String	Size	Depth (ft)	Pulled (ft)	Comment	
PROD	4.5	3875	0	w/125 sxs cmt	\$125.94
SURF	8.625	253	0	w/200 sxs cmt	

Well Type: EOR UIC Docket No: E27357.1 Date/Time to Plug: 08/14/2006 1:00 PM
Plug Co. License No.: 33612 Plug Co. Name: GEIST, RON DBA WILDCAT WELL SERVICE
Proposal Rcvd. from: JEREMY ULRICH Company: ENERGY THREE, INC. Phone: (785) 637-5321

Proposed Plugging Method: Ordered out 255 sxs 60/40 pozmix - 10% gel - 600# hulls.
Well perfed at 800' - squeezed with 100 sxs; 1340' w/240 sxs.
Squeezed 125 sxs top down - left packer in the hole.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/14/2006 7:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Cut tubing off at 3650' - leaving AD-1 packer in the hole.
Pulled up to 3500' - mixed and circulated cement with 225 sxs and 100# hulls.
POOH. Topped with 30 sxs cement.
Hooked up to the annulus - instant pressure.

Perfs:

Top	Bot	Thru	Comments
3788	3794		

INVOICED
DATE 8-17-06
2007060396


RECEIVED
AUG 16 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

AUG 15 2006

PT

ENERGY THREE
GORHAM KS 67640

29-09S-22W
C S/2 NE SW

#3 BRASSFIELD OWWO

site: 8-1/2 S & 1-3/4 E OF HILL CITY KS cy: GRAHAM API: 15-065-21398
contr: UNKNOWN field: RED LINE NW
opd: NONE
fr date 05/19/97 spd date 10/15/96 drlg comp 10/15/96 card issued 05/19/97 last revised 05/19/97

ELV: 2367 KB, 2362 GL LOG
tops.....depth/datum
ANH.....1888 + 479
HEEB.....3583 -1216
TOR.....3610 -1243
LANS.....3625 -1258
BKC.....3649 -1482
LTD OLD.....3865 -1498
RTD OLD.....3870 -1503

IP status:
INJ, LKC 3777-3793 OA, 11/14/96
NOTE: CORR 5/12/97 - CORR RTD (WAS 3876)
OLD INFO: OPERATOR WAS ENERGY THREE, 3
BRASSFIELD, SPD 04/06/81, 04/12/81 8-5/8" 253 / 200
SX, 4-1/2" 3864 / 125 SX, OIL, P 15 BOPD, NW, LKC
3808-3811, 08/07/81 (CARD ISSUED 08/13/81)
CONTR: BIG THREE DRLG
NO CORES OR DSTS
MICT - CO, PF (LKC) 3808-3811, W / 4 SPF, AC 2000 GAL
(11%), SWB LD, SWB 12 BO & TR W, POP, IPP 15 BOPD,
NW, 8/7/81
NEW INFO: FR 05/19/97, REWORKED 10/15/96 DC
10/15/96

MICT - CO, SQZ'D OLD PFS (LKC 3808-3811) W/225 SX, PF FOR SQZ 4/1750, PLUG AT 3400 &
PKR AT 835, SQZ'D W/240 SX, PF FOR SQZ 4/800, PLUG AT 3400 & PKR AT 600, SQZ'D W/100
SX, SQZ SURF DWN W/125 SX, DO CMT, PF (LKC) 3777-3780, 3790-3793, W / 4 SPF, NO
TRTMNT RPTD, SET 2-3/8" TBG AT 3760, NO PKR, CONVERTED TO WIW - INJECTION RATE
125 BWPD, 11/14/96