

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-21153-00-00  
Spot: SENWSW Sec/Twnshp/Rge: 29-9S-22W  
1650 feet from S Section Line, 4000 feet from E Section Line  
Lease Name: BRASSFIELD Well #: 1  
County: GRAHAM Total Vertical Depth: 3890 feet

Operator License No.: 5430  
Op Name: ENERGY THREE, INC.  
Address: 1437 OLD SQUARE RD #201A  
JACKSON, MS 39211

String	Size	Depth (ft)	Pulled (ft)	Comment	
PROD	4.5	3889	0	w/100 sxs cmt	\$ 126.43
SURF	8.625	211	0	w/160 sxs cmt	

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/14/2006 10:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: JEREMY ULRICH Company: ENERGY THREE, INC. Phone: (785) 637-5321

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Interval of annulus squeezes and amounts unknown.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/14/2006 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 215 sxs cement with 400# hulls.  
S.I.P. 100#.  
Hooked up to the annulus and pumped 10 sxs cement.  
S.I.P. 500#.

Perfs:

INVOICED  
DATE 8-17-06  
2007060396


RECEIVED  
AUG 16 2006  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

Form CP-2/3

AUG 15 2006

PERF

ARROWHEAD PETROLEUM INC.  
400 N WOODLAWN, SUITE 29  
WICHITA, KS

#1 BRASSFIELD

29-9-22W  
SE NW SW

CONTR BIG SPRINGS DRLG. CO. CTY GRAHAM

GEOL STEPHEN B POWELL FIELD RED LINE NW

E 2390 KB CM 7/30/79 <sup>CARD</sup> ISSUED 9/15/79 IP P 48 BOPD  
LKC 3837-3840

API 15-065-21,153

+	+	+	+
+	+	+	+

LOG	TOPS	DEPTH	DATUM
ANH		1915	+ 475
B ANH		1951	+ 439
TOP		3383	- 993
HEEB		3605	-1215
TOR		3630	-1240
LANS		3642	-1253
MUN CR		3765	-1375
BKC		3870	-1480
LTD		3889	-1499
RTD		3890	-1500

8-5/8" 211/160sx, 4 1/2" 3889/100sx  
DST (1) 3794-3814/30-30-30-30, 20' M,  
SIP 61-61#, FP 40-40/40-40#  
DST (2) 3814-53/30-45-60-45, 210' GIP,  
90' VHO&GCM, SIP 326-326#, FP 61-  
61/61-61#  
MICT - CO, PF 6/3837-3840, AC 1250 GAL,  
SWB DWN, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS