

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01024-00-00
Spot: NESWSE Sec/Twnshp/Rge: 21-7S-25W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: BLAZIER Well #: 1
County: GRAHAM Total Vertical Depth: 4172 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4172	0	200 sx
SURF	8.625	238	0	200 sx

\$135.59

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2006 10:30 AM
Plug Co. License No.: 33555 Plug Co. Name: K C WELL SERVICE, INC.
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 272-1023

Proposed Plugging Method: Ordered 240 sxs Midcon II Cement and 600# hulls.
Plug through tubing.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2006 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 238' w/200 sxs cement.
5 1/2" production casing set at 4172' w/200 sxs cement.
TD 4172'. Solid tag at 3781' with sandline.
08/01/2006: Perforated production casing at 2175' - 1400' - 290'.
Ran tubing to 2480' - pumped 55 sxs cement with 300# hulls.
Pulled tubing to 2380' - pumped 75 sxs cement with 300# hulls.
Pulled tubing to 500' - pumped 60 sxs cement - cement to surface.
Connected to 5 1/2" production casing - pumped 40 sxs cement.
Max. P.S.I. 50#. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
3796	3804		
3785	3793		

INVOICED
DATE 8-17-06
2007060392

RECEIVED
AUG 16 2006
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #10,473.

Plugged through: TBG

District: 04

Signed Dave Dipman
(TECHNICIAN)

AUG 04 2006