

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-27034-00-00  
Spot: NENWSWNW Sec/Twnshp/Rge: 30-25S-14E  
1590 feet from N Section Line, 470 feet from W Section Line  
Lease Name: NORDMEYER Well #: 24-06  
County: WOODSON Total Vertical Depth: 1368 feet

Operator License No.: 30345  
Op Name: PIQUA PETRO, INC.  
Address: 1331 XYLAN ROAD  
PIQUA, KS 66761

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40	0	

\$ 44,460

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/26/2006 1:00 PM  
Plug Co. License No.: 30567 Plug Co. Name: RIG 6 DRILLING CO., INC.  
Proposal Rcvd. from: BUD SEIFER Company: RIG 6 DRILLING CO., INC. Phone: (620) 939-4330

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD BORE TO 1368'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT 1368', TO PLACE A 50' CEMENT PLUG AT 800', AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: FRANK GUILFOYLE WitnessType: NONE  
Date/Time Plugging Completed: 05/26/2006 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

TUBING WAS RAN INTO THE WELL TO 1368'. 20 SACKS OF CEMENT WERE PUMPED THROUGH THE TUBING TO 1368'. THE TUBING WAS PULLED TO 800' AND 20 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE TUBING WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE TUBING UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED  
KCC DISTRICT #3

AUG 9 2006 CPT

CHANUTE, KS

INVOICED

8-15-06  
2007060385

RECEIVED  
AUG 14 2006  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

PST