

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19208-00-00

Spot: SESESW Sec/Twnshp/Rge: 20-14S-13W

330 feet from S Section Line, 2970 feet from E Section Line

Lease Name: OPDYCKE

Well #: 2

County: RUSSELL

Total Vertical Depth: 3047 feet

Operator License No.: 7986

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	8	2411	0	w/unknown sxs cmt
PROD	7	2910	0	w/unknown sxs cmt
SURF	10	744	0	w/unknown sxs cmt

\$ 99.03

Op Name: OPDYCKE LEASE PARTNERS, A GENE

Address: P.O. BOX 311
RUSSELL, KS 67665

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/28/2006 12:30 PM

Plug Co. License No.: 31172

Plug Co. Name: L & M WELL SERVICING, INC.

Proposal Rcvd. from:

Company: OPDYCKE LEASE PARTNERS

Phone: (785) 483-4563

Proposed Order 400 sxs 60/40 pozmix - 600# hulls.

Plugging Pump through tubing.

Method: Tie on top and squeeze.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/28/2006 3:15 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Perforated at 150' - 700' - 1350'.

Tubing at 1780' - pumped 150 sxs cement with 600# hulls.

Pulled tubing to 890' - pumped 100 sxs cement - circulated.

Pulled tubing out - tied on casing and squeezed 20 sxs cement.

Max. P.S.I. 800#. S.I.P. 400#.

INVOICE # 8-15-06
DATE 2007060384
TIME


RECEIVED
AUG 14 2006
KCC WICHITA

Remarks: QUALITY CEMENTING-TICKET #1060.

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

STEARNS

#2 OPDYCKE

20-14-13W
SE SE SW


Contr. _____ RUSSELL County

5 1772 Comm 5-9-41 Comp. 6-25-41 IP 1940 BOPD

Tops	Depth	Datum
ANHY	730	
LANS	2910	
TD	3047	

Casing
10" 744
8" 2411
7" 2910

A/500; SG 1745-55
SO 2295-2300 & 2982-85



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS