

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29391-00-00

Spot: SESWNWSE

Sec/Twnshp/Rge: 19-23S-20E

1380 feet from S Section Line,

2045 feet from E Section Line

Lease Name: ADAMS

Well #: N-2

County: ALLEN

Total Vertical Depth: 1380 feet

Operator License No.: 33120

Op Name: DEREK LEON RHODES

Address: 123 78 SE OHIO RD.
KINCAID, KS 66039

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20	0	

\$ 44.85

Well Type: DH

UIC Docket No:

Date/Time to Plug: 07/26/2006 1:00 PM

Plug Co. License No.: 33120

Plug Co. Name: DEREK LEON RHODES

Proposal Revd. from: DEREK THODES

Company: DEREK LEON RHODES

Phone: (620) 496-5275

Proposed
Plugging
Method:

THIS WELL CONSISTED OF AN UNCASD BORE TO 1380'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT 500' AND A CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: JOHN ALMOND

WitnessType: NONE

Date/Time Plugging Completed: 07/26/2006 5:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

TUBING WAS RAN INTO THE WELL TO 1380'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE TUBING TO 1380'. THE TUBING WAS PULLED TO 500' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE TUBING WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE TUBING UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 110 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3

AUG 9 2006 CPT

CHANUTE, KS

INVOICED
DATE 8-15-06
2007060380

RECEIVED
AUG 14 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)

PEI