

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22641-00-00
Spot: S2NE Sec/Twnshp/Rge: 31-31S-12W
1650 feet from N Section Line, 1490 feet from E Section Line
Lease Name: HALL Well #: 1
County: BARBER Total Vertical Depth: 4599 feet

Operator License No.: 9482
Op Name: NATIONAL PETROLEUM RESERVES, I
Address: 250 N. ROCK RD., STE 130
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4470		
PROD	4.5	4579	2305	WITH 235 SX CMT
SURF	8.625	346		WITH 215 SX CMT

\$ 149.47

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/21/2006 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 3560' & 4 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2006 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3560' & PUT 4 SX CMT ON TOP OF SAND BRIDGE. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 370' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4508	4515		
3632	3634		
3624	3629		

INVOICED
DATE 8-10-06
2007060362

RECEIVED


AUG 09 2006

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

Form CP-73

ACT