

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-20089-00-01  
Spot: NWSWNW Sec/Twnshp/Rge: 17-15S-17W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: LEIKER C Well #: 2  
County: ELLIS Total Vertical Depth: 3564 feet

Operator License No.: 5242  
Op Name: PETROLEUM MANAGEMENT, INC.  
Address: 14201 EAST CENTRAL  
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3561	0	w/200 sxs cmt
SURF	8.625	1131	0	w/450 sxs cmt

\$ 115.83

Well Type: EOR UIC Docket No: E15655.1 Date/Time to Plug: 08/03/2006 4:00 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: GARY REED Company: EXPRESS WELL SERVICE & SUPPL Phone: (785) 735-9405

Proposed Plugging Method: Ordered 200 sxs 60/40 poMix - 10% gel - 400# hulls.  
Dakota 167'-467'. Anhy.1119'-1155'. Salt 1501'-1771'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/03/2006 5:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service sanded off bottom to 3285' and topped with 4 sxs cement.  
Cut casing at 1905' - pulled to 1775'. Quality rigged to casing - pumped 80 sxs 60/40 pozmix with 300# hulls mixed in.  
Pulled casing to 1190' - pumped 35 sxs 60/40 pozmix with 100# hulls mixed in.  
Pulled casing to 510' - pumped 35 sxs.  
Pulled casing to 170' - pumped 40 sxs cement to circulate cement to surface.  
Pulled casing and topped with 10 sxs.  
Hole was standing full of cement.

Perfs:

Top	Bot	Thru	Comments
3401	3405		

INVOICED  
AUG 10 2006  
2007060304

RECEIVED

AUG 09 2006

KCC WICHITA

Remarks: QUALITY CEMENTING

Plugged through: CSG

District: 04

160

Signed

(TECHNICIAN)

AUG 04 2006

PT

PETROLEUM MANAGEMENT, INC.

#2 LEIKER 'C'

17-15-17W  
NW SW NW

Contr. RED TIGER DRLG

Cty. ELLIS

Geol.

Pool. WHEATLAND EAST

E. 1972 KB Cm. 7/15/67 Cp. 10/12/67 IP 93 BOPD + 10% W

LANS 3401-05

API 15-051-20,089

P 120 BOPD, NW/ARB 3561-62

LOG Tops	Depth	Datum	Csg. 8" 1131 4" 3561
ANHY	1119	+ 853	DST 3278-3360/60", 60' SIP, 30'
B/ANHY	1155	+ 817	WM O/S, 180' MDY WTR, BHP
TOP	2950	- 978	512-481#, FP 96-118#
HEEB	3218	-1246	DST 3386-3449/1', GB, 2340' SIP,
TOR	3238	-1266	90' GSY OCM, 180' VHO&JCM,
LANS	3270	-1298	180' G&MCO, BHP 1088-1067#,
BKC	3500	-1528	FP 149-192#
B/PENN CG	3545	-1573	DST 3460-3510/1', 15' DM, BHP
ARB	3556	-1584	128-32#, FP 21-21#
LTD	3555	-1583	DST 3558-62/1', 10' VSOCM, BHP
RTD	3562	-1590	86-86#, FP 11-11#
DDTD	3564	-1592	COTD 3562, NS, DD 3564, TU 1500'
			OIH/12 HRS, SWB 2.5 BOPH/4 HRS,
			A 500, 3 BOPH, /3402-05 & 3422-24,
			3440-42, SWB LD, SWB 8 BOPH, NY
			PMP 120 BOPD, NW/ARB 3561-62

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS