

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20226-00-00
Spot: NENE Sec/Twnshp/Rge: 31-21S-33W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: MAUNE A Well #: 10
County: FINNEY Total Vertical Depth: 4824 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 12950 E. 13TH
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1200		WITH 2 SX CMT
CIBP		4400		WITH 2 SX CMT
CIBP		4726		WITH 1 SX CMT
PROD	5.5	4824	0	WITH 150 SX CMT
SURF	8.625	362		WITH 300 SX CMT

\$156.78

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/27/2006 10:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL CO. Phone: (316) 636-2090

Proposed Plugging Method: AS PER KCC - SET CIBP@ 4300' W/2 SKZ CMT - TEST CSG TO 500# SET 2ND CIBP@ 1200' W/ 2 SKS CMT - PERFORATE 5 1/2" CSG, 2 HOLES @ 1150' - TEST FOR CIRCULATION - PUMP 200 SKS 60/40 W/ 6% GEL DOWN 5 1/2" (CIRCULATE CEMENT TO SURFACE) IF NO CIRCULATION - PUMP 200 SKS 60/40 W/ GEL DOWN 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/27/2006 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4726' WITH 1 SX CMT. CIBP @ 4400' WITH 2 SX CMT. CIBP @ 1200' WITH 2 SX CMT. PERFORATE AT 1150'. PUMP 80 SX CMT, 100# HULLS & 100 SX CMT. PRESSURE TO 800#. NO BLOW OR RETURNS UP 5 1/2" X 8 5/8" ANNULUS. HOLDING 70 PSI AFTER 1 HOUR. PUMP 200 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS AT 200#, DECREASING TO 50#. HELD AT 20#.

Perfs:


Top	Bot	Thru	Comments
4731	4733		

INVOICED
8-11-06
20070603
RECEIVED
AUG 11 2006
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Ken Jehlik

(TECHNICIAN)