

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-2081916-00-04
 API NUMBER unavailable

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Gentry
 WELL NUMBER old cable tool hole
4900' Ft. from S Section Line
660' Ft. from E Section Line
 SEC. 1 TWP. 30 RGE. 15 (E) or (W)
 COUNTY Wilson
 Date Well Completed unknown
 Plugging Commenced 2-28-02
 Plugging Completed 3-1-02

LEASE OPERATOR James D. Lorenz

ADDRESS 543A 22000 Rd. Cherryvale, Kansas

PHONE# 620 328-4433 OPERATORS LICENSE NO. 9313

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-27-02 (date)

by Tony Williams (KCC District Agent's Name).

Is ACO-1 filed? unknown if not, is well log attached? no

Producing Formation unknown Depth to Top _____ Bottom RECEIVED

Show depth and thickness of all water, oil and gas formations.

MAR 21 2002

OIL, GAS OR WATER RECORDS

CASING RECORD

KCC WICHITA

Formation	Content	From	To	Size	Put in	Pulled out
surface		0'	?	10"		
production		0'	850'	2"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Old cable tool hole with 2" down inside 10" surface casing. 1" pipe ran down inside 2" down to 850'. Ran 1" down backside 750' down backside. Cement pumper pumped cement down inside to surface, then hooked onto pipe. ran down backside, pumped cement to surface both 1" pipes pulled and well topped off using 150 sx. Portland cement. ***CONTINUED ON BACK***

Name of Plugging Contractor L & S Well Service License No. 9313

Address 543A 22000 Rd. Cherryvale, KS 67335-8515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: James D. Lorenz

STATE OF Kansas COUNTY OF Labette, ss.

James D. Lorenz (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Helen S. Lorenz

(Address) 543A 22000 Rd. Cherryvale, KS

District # 43 SUBSCRIBED AND SWORN TO before me this 13th day of March, 2002

Janet George
 Notary Public


My Commission Expires: May 9, 2002

RECEIVED

KCC

MAR 19 2002

Chanute KS



Form CP-1
 Revised 05-88

OR

2-1-02 Cement found with worm hole & salt water coming through. Flat plate weld to surface casing w/2" pipe coming out. 2" pipe hooked onto with cement pump and pumped cement until it came up the backside. Forced cement down 2" pressure up to 500 lbs. using additional 60 sx. Portland. Well was shut in.