

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Berexco, Inc.

Address: PO Box 723

Phone: (785) 628-6101 Operator License #: 5363

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)

The plugging proposal was approved on: 7-24-06 (Date)

by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

ARB Depth to Top: 3804 Bottom: 3809 T.D. 3820
RTD Depth to Top: Bottom: T.D. 3820

API Number: 15-165-20039-00-00

Lease Name: Ohnmacht

Well Number: 4

Spot Location (QQQQ): NW - NW - SW - 2310 Feet from North / South Section Line

4950 Feet from East / West Section Line

Sec. 32 Twp. 16 S. R. 19 East West

County: Rush

Date Well Completed: 6-67

Plugging Commenced: 7-24-06

Plugging Completed: 7-25-06

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Rows include ARB oil formations.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

In hole w/ 2-3/8 tbg to 3400'. TIH w/ tbg to 3668'. Mix 25sks 100# hulls 60/40 6% gel. Pull tbg to 1215' & mix 75 sks 60/40 6% circ cmt to surface. TOH w/ tbg. Tie onto 4-1/2 csg and fill w/ 15sks. Tie onto 8-5/8 & pump 30 sks down 8-5/8. Well plugged but lockset was not pulled.


Name of Plugging Contractor: Berexco Inc. License #: 5363

Address: PO Box 723 Hays, KS 67601

Name of Party Responsible for Plugging Fees: Mark Leiker

State of KS County, Ellis, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Mark Leiker

(Address) PO Box 723 Hays KS 67601

My Appt. Exp. 14 day of August 20 06 My Commission Expires: 9-19-09

RECEIVED AUG 18 2006 KCC WICHITA

Pkt

Quality Well Service, Inc.

Invoice

**401 West Main
Lyons, KS 67554**

Date	Invoice #
7/17/2006	791

Bill To
M.A. Yost Operations, Inc. PO Box 811 Russell, KS 67665

P.O. No.	Terms	Lease Name
	net	Landon 1

Description	Qty	Rate	Amount
Rig Time	12.5	155.00	1,937.50T
Torch		75.00	75.00T
Welder		75.00	75.00T
nipple, 5 1/2"		15.00	15.00T
Backhoe	4.5	70.00	315.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
<p>7-11-06 Drove to location, raised pole, checked hole with baler, hit bridge at 150', pushed bridge to 450', wouldn't move, moved pumping unit with backhoe, ran tubing down to 510', had Quality Oilwell Cementing circulate hole, ran tubing down to 930', dug cellar and pit, pumped 90 sacks, 3 hulls, circulated to surface, pulled tubing out, cut nipple out of 5 1/2" collar, collar was bad, welded nipple in collar, pumped 150 sacks, 2 hulls down 5 1/2", max pressure 500 psi, shut in 200 psi, tied on to 8 5/8", pressured up to 1200 psi, tore down rig, drove home.</p> <p>7-12-06 Drove to location, cut 5 1/2" - 8 5/8" off 4' below ground, cleaned up location.</p>			

RECEIVED
AUG 17 2006
KCC WICHITA

Subtotal	\$2,452.50
Sales Tax (7.3%)	\$179.03
Total	\$2,631.53