

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Kenneth Parten
Address: 112 S. Broadway, St. John, KS. 67576
Phone: (620) 549-3973 Operator License #: 7202
Type of Well: Gas EOR KCC & 18100 PKT per UICDF W.W. Docket #: E 18179.1
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: August 1, 2006 (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: 4161' T.D. 4193'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 185-00373 -00-01
Lease Name: Henderson
Well Number: #2
Spot Location (QQQQ): _____ - NW - SW - SE
990 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 7 Twp. 24 S. R. 13 East West
County: Stafford
Date Well Completed: 8/24/56
Plugging Commenced: 8/02/06
Plugging Completed: 8/04/06


Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	229'	8-5/8"	229'	0'
	Production	0'	3960'	5-1/2"	3960'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
M.I.R.U. Released Model "G" packer. Pulled 1 joint (2-3/8") and 34 joints (2-1/16") tubing. Tubing parted in the collar, coming out of the hole. Ran - 2-1/16"x4-7/8" overshot and tubing. Got down to 300'. Pulled tools out of hole. Ran 2-7/8" tubing, open-ended down to 502' - casing was parted from 300'-500'. Pulled tubing out of hole. Ran 2-1/16" tubing in hole. Worked tubing down through part. Went down to 1120' with tubing - got ready to plug. Hooked up Copeland to cement well. Pumped 325 sacks down casing. Pulled tubing out of hole. Hooked up to surface - pumped 125 sacks. Rigged down and moved off.

Name of Plugging Contractor: D.S.&W. Well Servicing, Inc. License #: 6901
Address: P.O. Box 231, Claflin, KS. 67525
Name of Party Responsible for Plugging Fees: Kenneth Parten

State of Kansas County, Barton, ss.
Edward S. Nernich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

 KAREN J. MITCHELL (Signature) Edward S. Nernich
Notary Public - State of Kansas
My Appt. Expires 4/13/2010 (Address) P.O. Box 231, Claflin, KS. 67525

SUBSCRIBED and SWORN TO before me this 14th day of August, 20 06
Karen J. Mitchell My Commission Expires: 4/13/2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
AUG 16 2006
KCC WICHITA
PKT