

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Petroleum Management, Inc.  
Address: 14201 E. Central, Wichita, KS 67230  
Phone: (316) 733-5600 Operator License #: 5242  
Type of Well: ENHR Docket #: E-15655  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 8/2/06 (Date)  
by: Herb Deines District 4 (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3556' Bottom: 3568' T.D. 3568'  
LKC Depth to Top: 3270 Bottom: 3500 T.D. NA  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 051-20089 - 00 - 01  
Lease Name: Leiker C  
Well Number: 2  
Spot Location (QQQQ): \_\_\_\_\_ - NW - SW - NW  
3630 Feet from  North /  South Section Line  
4950 Feet from  East /  West Section Line  
Sec. 17 Twp. 15 S. R. 17  East  West  
County: Ellis  
Date Well Completed: 8/14/67  
Plugging Commenced: 8/4/06  
Plugging Completed: 8/4/06

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |         | Casing Record (Surface Conductor & Production) |      |       |        |                                       |
|---------------------------|---------|--|------|-------|--------|---------------------------------------|
| Formation                 | Content | From   | To   | Size  | Put In | Pulled Out                            |
|                           |         | 0  | 1123 | 8.625 | 1123   | 0                                     |
|                           |         | 0  | 3562 | 4.50  | 3562   | <del>1905</del> KCC 8/15/06 per CPA/B |
|                           |         |  |      |       |        |                                       |
|                           |         |  |      |       |        |                                       |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Shot off casing @ 1905'; pulled to 1775' spot 80 sx + 300# hulls ; pulled to 1175' spot 35 sx + 100# hulls; pulled to 525' spot 35 sx ; pulled to 150' and circulated cement to surface with 50 sx. All cement 60/40 Poz + 10% gel

Name of Plugging Contractor: Express Well Service License #: 6426

Address: P.O. Box 19, Victoria, KS 67671-0019

Name of Party Responsible for Plugging Fees: Petroleum Management, Inc.

State of Kansas County, Sedgwick, ss.


Gary L. Reed as Agent of Operator (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Gary L. Reed, as Agent  
(Address) 14200 Brookline Ct Wichita Ks 67230

SUBSCRIBED and SWORN TO before me this 7 day of August, 20 06

Deborah R. Haddock My Commission Expires: 4/28/09  
Notary Public  
Deborah R. Haddock

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



RECEIVED  
AUG 08 2006  
KCC WICHITA

PT