

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 075-00009 -00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date Spud - 4/18/57

Well Operator: Chesapeake Operating, Inc. KCC License #: 32334

Address: P.O. Box 18596 City: Oklahoma City

State: Oklahoma Zip Code: 73154-0496 Contact Phone: ( 405 ) 767 - 4078

Lease: Bradshaw Well #: 1-36 Sec. 36 Twp. 22 S. R. 41  East  West

     -      - NW - SE Spot Location / QQQQ County: Hamilton

1980 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket #       ENHR Docket #       Other:     

Conductor Casing Size:      Set at:      Cemented with:      Sacks

Surface Casing Size: 13-3/8" Set at: 274' Cemented with: 250 Sacks

Production Casing Size: 8 5/8" Set at: 2782' Cemented with: 400 Sacks

List (ALL) Perforations and Bridgeplug Sets: [2573, 2624, 2633 - 2646, 2652 - 2660, 2685 - 2695, 2705, 2743 - All squeezed off].

[2548 - 2564, 2590 - 2610 Producing]

Elevation: 3503' ( G.L. /  K.B.) T.D.: 5417' PBTD: 2625' Anhydrite Depth: 2058'

(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): See attached sheet

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 28 2006  
CONSERVATION DIVISION  
WICHITA, KS

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why?     

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Bud Neff

Phone: ( 620 ) 277 - 0803

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996

Address:      Phone: ( 785 ) 483 - 2627

Proposed Date and Hour of Plugging (if known?):     

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/24/2006 Authorized Operator / Agent:  (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 28 2006

CONSERVATION DIVISION  
WICHITA, KS

Bradshaw 1-36  
36-22S-41W  
Hamilton Co., KS  
CP-1 (Pg. 2 of 2)

**Plugging Procedure:**

1. MIRU Wireline, MIRU Cementers, dig out bradenhead.
2. PU 8 5/8" CIBP, RIH and set at 2500', cap with 2 sx cmt, POOH, PU 8 5/8" CIBP, RIH and set at 1160', cap with 2 sx, POOH. Pressure test casing.
3. PU squeeze gun, RIH to 1140', perforate 4 squeeze holes, POOH, RDMO Wireline. Tie onto casing EIR, attempt to circulate to surface. Mix and pump 300 sx cement.
4. Tie onto 4 1/2"x 7" annulus, attempt to establish pump in, if able to pump into annulus mix and pump 100 sx cement. RDMO cementers.

Weld on cap, clean up location



Regulatory Department

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 28 2006  
CONSERVATION DIVISION  
WICHITA, KS

August 25, 2006

**VIA UNITED PARCEL SERVICE**

Kansas Corporation Commission  
Conservation Division  
Finney State Office Building  
130 South Market, Room 2078  
Wichita, Kansas 67202

Re: Bradshaw 1-36  
36-22S-41W  
Hamilton Co., KS  
API #15-075-00009

Dear Sir or Madam:

Enclosed is a Form CP-1 for the referenced well.

If additional information is required, please call Jim Reisch at (405) 767-4078 or the undersigned at (405) 767-4775.

Sincerely,

Aletha M. Dewbre-King  
Permitting Agent

**Enclosures**

xc (via e-mail): Jim Reisch, Bud Neff, Holly Hicks, Stacy Gilbert  
Carol Fehrenbacher, Brittany Mincey, Carol Holden

W:\RegOps\State\_Regulatory\_Permittin\Regulatory KS\~ks\CP-1 (Well Plugging App)\Correspondence\Bradshaw 1-36.doc