

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
**This Form must be Typed**  
**Form must be Signed**  
**All blanks must be Filled**

API # 15 - 047-20672-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 6/24/80.

Well Operator: Marlin Oil Corporation KCC License #: 9228

Address: PO Box 14630 Oklahoma City, OK. 73113 City: Oklahoma City

State: Oklahoma Zip Code: 73113 Contact Phone: ( 405 ) 478 - 1900

Lease: BELCHER Well #: 1 Sec. 16 Twp. 26 S. R. 18  East  West

NE/4 - SW/4 - NW/4 Spot Location / QQQQ County: Edwards

1650 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 372' Cemented with: 275 Sacks

Production Casing Size: 4-1/2" Set at: 4849' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perforations: 4682-4704', 4329-4331', 4282-4287', 4228-4232'. CIBP set at 4650'.

Elevation: 2185' / 2194' ( G.L. /  K.B.) T.D.: 4868' PBTD: 4650' Anhydrite Depth: 1240'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Displace 20 sx cement plug with mud to plug perms at 4228-4331'.

Cut off 4-1/2" casing as deep as possible. Place 75 sx cement plug from 422-322' and a 10 sx cement plug from 34-4'. Weld on ID cover plate.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: Dick Lynn

Marlin Oil Corp. Phone: ( 405 ) 818 - 8738

Address: P.O. Box 14630 City / State: Oklahoma City, OK 73113

Plugging Contractor: Orr Enterprises, Inc. KCC License #: 33338

Address: P.O. Box 1706, Duncan, OK 73534 Phone: ( 580 ) 251 - 9618

Proposed Date and Hour of Plugging (if known?): within the next 60 days

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/22/06 Authorized Operator / Agent: \_\_\_\_\_



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

AUG 25 2006

KCC WICHITA

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Marlin Oil Corporation  
PO Box 14630  
Oklahoma City, OK 73113-0630

August 28, 2006

Re: BELCHER #1  
API 15-047-20672-00-00  
NESWNW 16-26S-18W, 1650 FNL 990 FWL  
EDWARDS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely



David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888