

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Berexco, Inc.
Address: PO Box 723 Hays KS 67601
Phone: (785) 628-6101 Operator License #: 5363
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8-10-06 (Date)
by: Jay Pfeifer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
ARB Depth to Top: _____ Bottom: 3837 T.D. 3841
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-163-03140-00-00
Lease Name: Glick
Well Number: 2
Spot Location (QQQQ): SE - NW - NE - KCC PPT
4290 Feet from North / South Section Line 8/23/06
1650 Feet from East / West Section Line per CP 2/3
Sec. 4 Twp. 10 S. R. 20 East West
County: Rooks
Date Well Completed: 11-1-48
Plugging Commenced: 8-10-06
Plugging Completed: 8-10-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
ARB	oil	0	215'	8-5/8	11-1-48	----
		0	3837 1/2'	5-1/2	11-1-48	-----

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Shot 2 holes @ 2200', 1800', 975', and 150'. Run 99 jts 2-3/8 tbg open ended to 3021'. Mix 115 sks 60/40 pos 10% gel 400# hulls.
Pull 50 jtsto 1507'. Mix 100 sks 60/40 pos 10% gel w/ 200 # hulls. Circ to surface. Pull tbg hook to 5-1/2. Mix 60 sks 60/40 pos 10% gel. Max pressure 600#, Shut in pressure 150#.

Name of Plugging Contractor: Berexco, Inc. License #: 5363
Address: PO Box 723 Hays, KS 67601
Name of Party Responsible for Plugging Fees: Bob Grant - Berexco, Inc
State of KS County, Ellis, ss. KCC 8/23/06 PPT per oper-Shanna **RECEIVED**
AUG 21 2006
KCC WICHITA

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Robert A Grant
(Address) PO Box 723 Hays, KS 67601



Subscribed and SWORN TO before me this 17 day of August, 20 06
Shanna Miller My Commission Expires: 9-19-09
Notary Public

PPT