

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: DOWNING NELSON OIL COMPANY, INC.
 Address: PO BOX 372 HAYS, KS 67601
 Phone: (785) 621-2610 Operator License #: 30717
 Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
 The plugging proposal was approved on: 07/20/06 (Date)
 by: Herb Deines (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
NONE Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 051-25,551-00-00
 Lease Name: KUHN-MUNK UNIT
 Well Number: 1-9
 Spot Location (QQQQ): _____ - NE - SE - NW
1790 Feet from North / South Section Line
2440 Feet from East / West Section Line
 Sec. 9 Twp. 14 S. R. 16 East West
 County: ELLIS
 Date Well Completed: 07/21/06
 Plugging Commenced: 10:00PM 07/20/06
 Plugging Completed: 1:30AM 7/21/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		SURFACE	223	8 5/8	222.88	NONE

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


1st Plug @ 3350' W/ 25 sks 5th Plug @ 40' W/ 10sks Circulated 1st Plug 15 minutes W/52 Vis Mud
 2nd Plug @ 1025' W/ 25 sks 15sks in Rat Hole Plugs Displaced with Mud
 3rd Plug @ 525' W/ 80 sks 10sks in Mouse Hole Total 205sks 60/40 Poz 6% Gel W/1/4 CF/sk
 4th Plug @ 275' W/ 40sks By Allied Cementing-Completed @ 1:30AM 7/21/06

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548
 Address: PO BOX 763 HAYS, KS 67601

Name of Party Responsible for Plugging Fees: Downing Nelson Oil Co., Inc.
 State of KS County, Ellis, ss.

Alan Downing (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) P.O. Box 372 Hays, KS 67601



and, SWORN TO before me this 16 day of August, 20 06
Michele L. Meier My Commission Expires: 7/28/09
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED

AUG 21 2006

KCC WICHITA

PHT