

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Eagle River Energy Corporation
Address: 7060 S. yale, Suite 609
Phone: (918) 494-8928 Operator License #: 31070
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: CP-1 submitted 07/25/06 (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Topeka Depth to Top: 3277 Bottom: 3281 T.D. 3619
Lansing-Kansas City Depth to Top: 3407 Bottom: 3527 T.D. 3619
Arbuckle Depth to Top: 3614 Bottom: TD T.D. 3619

API Number: 15-163-01578-00-00
Lease Name: Hilgers
Well Number: 2
Spot Location (QQQQ): _____ - NE - SW - NW
1650 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 30 Twp. 9 S. R. 18 East West
County: Rooks
Date Well Completed: 09/63
Plugging Commenced: 08/09/06
Plugging Completed: 08/10/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Topeka	oil, water	3277	3281	8 5/8; 5 1/2	161; 3614	None
Lansing-Kansas City	oil, water	3407	3527	8 5/8; 5 1/2	161; 3614	None
Arbuckle	oil, water	3614	TD	8 5/8; 5 1/2	161; 3614	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 3/8 tubing to 1150; circulate w/130 sx cement. Lay out all tubing, tied on to 5 1/2 csg pumped 260 sx cement w/300# c/s hulls. Max. pressure @ 1000#. Shut-in @ 200#. Pumped 50 sx cement between 8 5/8 and 5 1/2, pressure @ 200#.

Name of Plugging Contractor: Plains, Inc. License #: 4072 **RECEIVED**
Address: P.O. Box 346, Ness city, KS 67560 **AUG 21 2006**
Name of Party Responsible for Plugging Fees: Eagle River Energy Corporation **KCC WICHITA**
State of Oklahoma County, Tulsa, ss.
Mark P. Godsey

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark P. Godsey
(Address) 7060 S. Yale, Suite 609, Tulsa, OK 74136

SUBSCRIBED and SWORN TO before me this 17th day of August, 20 06
Dora Stewart My Commission Expires: 10-25-08
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials: PM