

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Gore Oil Company
Address: P.O. Box 2757, Wichita, KS 67201-2757
Phone: (316) 263-3535 Operator License #: 5552
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8-2-06 (Date)
by: Richard Williams (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3660' Bottom: 3668' T.D. 3668'

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 195-00723 -00-00
Lease Name: Hedstrom
Well Number: #3
Spot Location (QQQQ): S/2 - NE
3300 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 3 Twp. 11 S. R. 21 East West
County: Trego
Date Well Completed: 12-23-55
Plugging Commenced: 8-2-06
Plugging Completed: 8-2-06

KCC 8/23/06
PPT per
CP 23

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Oil, Water	0	221'	8 5/8"	221'	0'
Production	Oil, Water	0	3661'	5 1/2"	3661'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run 22 jts, 710' of 2 7/8" tbg in well to plug with. Hook up to tbg and pump 5 bbls water, had blow on 5 1/2" & 8 5/8" both. Pump 40 sx SMD cement down tbg and circulated cement out 5 1/2" casing. Pull tbg out of hole. Hook up to 5 1/2" casing and pump 60 sx SMD @ 13#/gal until cement circulated out 8 5/8". Shut in 8 5/8" and pump 100 sx @ 12# w/1sx hulls, max psi 350. Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 67560 32382
Address: P.O. Box 466, Ness City, KS 67560

RECEIVED

AUG 21 2006

KCC WICHITA


Name of Party Responsible for Plugging Fees: Gore Oil Company
State of Kansas County, Sedgwick, ss.

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M Jack

(Address) Wichita, KS



SUBSCRIBED and SWORN TO before me this 17 day of August, 20 06
Rebecca K. Crawford My Commission Expires: 3-20-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PPT