

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Gore Oil Company  
Address: P.O. Box 2757, Wichita, KS 67201-2757  
Phone: (316) 263-3535 Operator License #: 5552  
Type of Well: SWD Docket #: E-18370  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 7-24-06 (Date)  
by: Richard Williams (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

API Number: 15-179-20069-00-02  
Lease Name: Pratt  
Well Number: #2 SWD per CP-1  
Spot Location (QQQQ): NW - NE - SW -  
2300 Feet from  North /  South Section Line  
3630 Feet from  East /  West Section Line  
Sec. 35 Twp. 8 S. R. 29  East  West  
County: Sheridan  
Date Well Completed: 2-4-68 (original)  
Plugging Commenced: 7-26-06  
Plugging Completed: 7-26-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	Oil, Water	0	221'	8 5/8"	221'	0'
Production	Oil, Water	0	4224'	4 1/2"	4224'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Run 1 1/4" tubing to 2000' and circulate for 2 hrs. Pulled to 1970' and Swift circulated 35 sx SMD cement to surface. Pulled tubing and pumped 14 sx cement down 2 7/8" casing. Hooked to 8 5/8" surface pipe and pressure to 500 psi with 1/2 sx cement. Hooked to 4 1/2" casing and pressured to 500 psi with 1/2 sx cement. Job complete. Darrel Dipman on location during plugging for KCC.

Name of Plugging Contractor: Swift Services, Inc. License #: 67560 32382  
Address: P.O. Box 466, Ness City, KS 67560

Name of Party Responsible for Plugging Fees: Gore Oil Company  
State of Kansas County, Sedgwick, ss.

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M. Jack  
(Address) Wichita, KS



My Appt. Exp. 3-20-07 and SWORN TO before me this 18th day of August, 20 06  
My Commission Expires: 3-20-07  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
AUG 21 2006  
KCC WICHITA

PKT