

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: MIDCO Exploration, Inc.
Address: 414 Plaza Drive, Suite 204 Westmont, IL 60559
Phone: (630) 655-2198 Operator License #: 5254
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: July 27, 2006 (Date)
by: District #2 (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4133 Bottom: 4141 T.D. 4141

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 095-20558-0000
Lease Name: Neville
Well Number: 1
Spot Location (QQQQ): 100' - E/C - SW -
1320 Feet from North / South Section Line
1420 Feet from East / West Section Line
Sec. 27 Twp. 28S S. R. 8 East West
County: Kingman
Date Well Completed: 4/1/77
Plugging Commenced: 7/27/2006
Plugging Completed: 7/27/2006 23 KCC 8/23/06 PCT per CP2/3.

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	213'	8 5/8"	213	-0-
		Surface	<u>4141'</u>	4 1/2"	4141	1209
			<u>4133'</u>	<u>KCC 8/23/06 PCT</u> <u>per CP2/3</u>		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dump 1 sack cement on plug. Cut and pull casing at 1209'. Plug using 145 sacks cement w/pozmix and gel.
First plug - 35 sacks @ 1209'; second plug - 35 sacks @ 637'; third plug - 75 sacks @ 259';
fill to surface.

Name of Plugging Contractor: Leiker Well Service, Inc. License #: 30891
Address: 271 W Jackson Great Bend, KS 67530
Name of Party Responsible for Plugging Fees: MIDCO Exploration, Inc.
State of Illinois County, DuPage, ss.
Earl J. Joyce, Jr. (Employee of Operator) or (Operator) on above-described well, being first duly


RECEIVED
AUG 21 2006
KCC WICHITA

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 414 Plaza Drive, Suite 204 Westmont, IL 60559

SUBSCRIBED and SWORN TO before me this 17th day of August 2006

Nancy L. Macyunas My Commission Expires: _____
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PCT