

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Jason Oil Company, LLC
Address: PO Box 701, Russell, KS 67665
Phone: (785) 483-8027 Operator License #: 33813

API Number: 15-167-39090-00-01
Lease Name: DILLNER OWWO KCC 8/28/06 Perc PPT
Well Number: 2

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

Spot Location (QQQQ): SE - NE - NE -
990 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 35 Twp. 13 S. R. 15 East West

The plugging proposal was approved on: _____ (Date)
by: Hubert Deines (KCC District Agent's Name)

County: Russell

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Date Well Completed: 11-18-81
Plugging Commenced: 7-17-06
Plugging Completed: 7-19-06

Producing Formation(s): List All (if needed attach another sheet)

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	930 200'	KCC 8/28/06 PPT per CP 1 PER PPT DAVE FUNK
				5 1/2	3303	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bridge at 450', shot holes at 1600', 950', 475', ran tubing down to 1800', pumped 250 sacks, 5 hulls, pulled tubing up to 900', pumped 50 sacks, circulated well, pulled tubing out, tied on to 8 5/8", pumped 50 sacks, max pressure 500, shut in 300, tied on to 5 1/2", pumped 20 sacks, max pressure 500, shut in 300, cut 5 1/2" - 8 5/8" off 4' below ground

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 401 West Main, Lyons, KS 67554

Name of Party Responsible for Plugging Fees: Jason Oil Company, LLC

State of KANSAS County, Russell, ss.


Jason Oil Company, LLC (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P. O. Box 701, Russell, KS 67665-0701

**RECEIVED
AUG 25 2006
KCC WICHITA**

SUBSCRIBED and SWORN TO before me this 22nd day of August, 20 06

Fred Weigel, Jr. My Commission Expires: July 18, 2010
Fred Weigel, Jr. Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PPT

Quality Well Service, Inc.

**401 West Main
Lyons, KS 67554**

Invoice

Date	Invoice #
7/21/2006	795

Bill To
Jason Oil Box 701 Russell, KS 67665

P.O. No.	Terms	Lease Name
	net	Dillner 2

Description	Qty	Rate	Amount
Rig Time	12	155.00	1,860.00T
Torch		50.00	50.00T
Water Truck	3	70.00	210.00T
Backhoe	1.5	70.00	105.00T
Phone Calls		15.00	15.00T
Clerical		20.00	20.00T
Fresh Water		20.00	20.00T
7-17-06 Drove to location, dressed up around cellar, raised pole, checked hole, had bridge at 450', beat bridge out with baler, drove home.			
7-18-06 Drove to location, had Perf-Tech shoot holes at 1600', 950', 475', ran tubing down to 1800', pumped 250 sacks, 5 hulls, pulled tubing up to 900', pumped 50 sacks, circulated well, pulled tubing out, tied on to 8 5/8", pumped 50 sacks, max pressure 500, shut in 300, tied on to 5 1/2", pumped 20 sacks, max pressure 500, shut in 300, tore down rig.			
7-19-06 Cut 5 1/2" - 8 5/8" off 4' below ground, backfilled cellar.			

Subtotal	\$2,280.00
Sales Tax (7.3%)	\$166.44
Total	\$2,446.44

**RECEIVED
AUG 25 2006
KCC WICHITA**