

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: ~~15-001-28135-00-00~~ 15-001-00203-00-00
Spot: S2SESW Sec/Twnshp/Rge: 6-25S-20E
155 feet from S Section Line, 3145 feet from E Section Line
Lease Name: JOHNSON Well #: W-7 7
County: ALLEN Total Vertical Depth: 800 feet

Operator License No.: 6137
Op Name: ENSMINGER, DONALD & JACK, A GEN
Address: 1446 3000 ST
MORAN, KS 66755

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	800	0	
SURF	8	20	0	

\$ 35.00

Well Type: ~~Oil~~ UIC Docket No: [REDACTED] Date/Time to Plug: 07/19/2006 9:00 AM
W.H.M. K.C.C. / [REDACTED]
Plug Co. License No.: 6137 Plug Co. Name: ENSMINGER, DONALD & JACK, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DAVE KENSEY Company: ENSMINGER, DONALD & JACK, A Phone: (620) 496-2300

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., TO PLACE A 50 CEMENT PLUG AT 500' AND TO CIRCULATE THE WELL FULL OF CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 07/19/2006 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:
1" PIPE WAS RAN INTO THE 2" CASING TO T.D.. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO T.D.. THE 1" PIPE WAS PULLED TO 500' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE 1" PIPE WAS PULLED TO 250' AND CEMENT WAS CIRCULATED TO SURFACE. THE 1" PIPE WAS PULLED AND RAN TO 250' IN THE ANNULUS BETWEEN THE CASING AND SURFACE CASING. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3
AUG 16 2006 CPT
CHANUTE, KS

Perfs:
INVOICED
DATE 8/24/06
SERIAL 2007060439

RECEIVED
AUG 23 2006
KCC WICHITA

Remarks: SPOT LOCATION ESTABLISHED VIA GPS SURVEY.

Plugged through:

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PKJ