

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-30421-00-01  
Spot: SESWNW Sec/Twnshp/Rge: 22-13S-20W  
2970 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: HONAS A OWWO Well #: 3  
County: ELLIS Total Vertical Depth: 3878 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE ROAD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1561		450 SX
PROD	4.5	3873	0	125 SX
SURF	8.625	162	0	75 SX

\$ 126.04

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/23/2006 2:00 PM  
Plug Co. License No.: 32278 Plug Co. Name: TENGASCO, INC.  
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
DV at 1561' set with 450 sxs.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/23/2006 4:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 160 sxs cement with 200# hulls.  
Max. P.S.I. 1700#. S.I.P. 1500#.  
Hooked up to the annulus and instant 500#.

Perfs:

Top	Bot	Thru	Comments
3873	3887		

INVOICED  
DATE 8/28/06  
INVOICE NO. 2007060453

RECEIVED  
AUG 25 2006  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Jay Pfeifer*  
(TECHNICIAN)

AUG 24 2006

PCT

ICER ADDIS #3 HONAS "A" "OWWO" 22-13-20W  
 P.O. DRAWER 8038 SE SW NW  
 WICHITA, KS.  
 CONTR L.D. DRLG. CO. CTY ELLIS

GEOL \_\_\_\_\_ FIELD PLEASANT

E 2229 KB CM 6/30/78 CARD ISSUED 9/21/78 P 25 BOPD + TR W  
 ARB 3872 $\frac{1}{2}$ -78

+	+	
+	+	

API NOT ASSIGNED

SMP	TOPS	DEPTH	DATUM
ANH	1553	+ 676	
TOP	3213	- 984	
HEEB	3465	-1236	
TOR	3485	-1256	
LANS	3505	-1276	
BKC	3760	-1531	
MARM	3807	-1578	
CHTY CONG	3816	-1587	
TD	3857	-1628	
DDTD	3878	-1649	

OLD INFO: OPERATOR WAS WOODMAN-TANNITTI #1 HONAS; SPD 12/30/66, SET 8" 162/75SX; COMPLETED AS D&A/CHTY CONG/1/26/67  
 DST (1) 3594-3660/1', REC 1100' MW, SIP 899-846#/20", FP 207-500#  
 DST (2) 3657-3720/1', REC 1100' MW, SIP 1337-1060#/20", FP 195-543#

NEW INFO: CO 3857', DD 3878', SET 4 $\frac{1}{2}$ " 3872 $\frac{1}{2}$ /125SX  
 DST (1) 3872-76/30-30-30-30, 15' OCM, SIP 936-884#, FP 10-10#, 21-21#  
 DST (2) 3872-3878/30-30-30-30, 90' GIP 90' BLK HOCM (30% OIL), SIP 1039-1029#, FP 21-21#, 21-21#  
 MICT - CO & AC 250, REC LD, POP

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS