

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21964-00-00
Spot: E2SENE Sec/Twnshp/Rge: 26-15S-25W
3390 feet from S Section Line, 330 feet from E Section Line
Lease Name: GIESS Well #: B-1
County: TREGO Total Vertical Depth: 4506 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4505	0	275/100 SX
SURF	8.625	220	0	140 SX

\$146.45

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/23/2006 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (785) 731-5615

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 10% gel - 200# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/23/2006 11:20 AM KCC Agent: PAT STAAB

Actual Plugging Report:

08/10/2006
Pumped 40 sxs 60/40 pozmix down 8 5/8" casing.
Max. P.S.I. 350#. S.I.P. 200#.
Pumped 50 sxs 60/40 pozmix and 3 sxs gel down 5 1/2" casing - locked up prematurely before adequate coverage of Dakota formation.
08/23/2006
Whitetail Crude drilled cement out of 5 1/2".
Ran tubing to 1995' - pumped 135 sxs with 100# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing - pumped 15 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
4471	4481		

INVOICED

DATE 8-29-06

2007060457

Remarks: SWIFT SERVICES, INC.-TICKET #10493.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

AUG 24 2006

RECEIVED
AUG 28 2006
KCC WICHITA

Form CP-2/3

PST

replacement card

JOHN JAY DARRAH, JR
WICHITA, KS 67202

26-15 -25W
90'N, C E/2 SE NE

#B-1 GIESS

site: 5-3/4 N & 3/4 W OF ARNOLD, KS

city: TREGO

API 15-195-21964

contr: MALLARD JV, INC

field: SPLITTER EAST

geol: WM. H. SHEPHERD

fr date 02/10/88

spd date 02/19/88

drlg comp 02/25/88

card issued 05/25/88

last revised 07/20/88

ELV: 2531 KB SMP

tops.....	depth/datum
ANH.....	1946 +585
HEEB.....	3836 -1305
TOR.....	3857 -1326
LANS.....	3878 -1347
BKC.....	4168 -1637
PAW.....	4291 -1760
FT SC.....	4373 -1842
CHER SH.....	4400 -1869
MISS DOL.....	4467 -1936
RTD.....	4506 -1975
NO LOG	

IP status:

OIL, P 15 BOPD, NW, MISS 4471-4481,
CORRECTION: 7/20/88 - ELEV WAS 2527 KB; WAS MISS
OH
CSG: 8-5/8" 220 / 140 SX, 5-1/2" 4505 / 375 SX
NO CORES
DST (1) 4395-4490 (CHER, MISS), / 30-30-45-45, REC
100' CLEAN GSY OIL, 150' SLI OCM (10% OIL, 10% G,
80% M), ISIP NA FSIP 1044# IFP 75# -75# FFP 129#
-140#
DST (2) 4490-4506 (MISS), / 30-30-45-45, REC 5' OIL,
55' OCM ISIP 873# FSIP 411# IFP 21# -21# FFP 54#
-54#
MICT - CO, PF (MISS DOL) 4471-4481, AC 1000 GAL
(10% MA) & 9000 GAL (10% GEL AC), GSO, T&R, POP, P
15 BOPD, NW, 4/24/88

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS