

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-11187-00-00  
Spot: NENWNENW Sec/Twnshp/Rge: 18-22S-12W  
5115 feet from S Section Line, 3465 feet from E Section Line  
Lease Name: HARMS W Well #: 1  
County: STAFFORD Total Vertical Depth: 3671 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3665	0	WITH 125 SX CMT
SURF	8.625	256		WITH 150 SX CMT # 119.31

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/17/2006 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/17/2006 11:50 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

TUBING STUCK IN HOLE 1115-1184'. BOTTOM OF TUBING AT 3640'. 8 5/8" X 5 1/2" ANNULUS CEMENTED AT SURFACE TO UNKNOWN DEPTH. SHOT TUBING AT 3590'. PUMPED 200# HULLS & 50 SX CMT DOWN TUBING. DISPLACED TO 3000'. TUBING AT 1085' BACKED OFF. PERFORATED 5 1/2" @ 750'. WENT TO BACK OFF AGAIN AND TUBING CAME APART AT 450'. PUMPED 60 SX CMT DOWN TUBING CIRCULATING CMT TO SURFACE UP 5 1/2". PULLED TUBING. PUMPED 100 SX CMT DOWN 5 1/2". MAXIMUM PRESSURE 400 PSIG. SHUT IN PRESSURE 0 PSIG.

Perfs:

Top	Bot	Thru	Comments
3665	3671	OH	


INVOICED  
DATE 8-30-06  
WR. NO. 2007060462

RECEIVED  
AUG 28 2006  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

Form CP-2/3

*PT*