

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

RECEIVED
KANSAS CORPORATION COMMISSION

API # 15 - 055-00818 -00-00 (Identifier Number of this well). This must be filled in for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 01/01/60

AUG 30 2006

Well Operator: Chesapeake Operating, Inc. (Owner / Company Name) KCC License #: 32334 (Operator's)

Address: P.O. Box 18496 City: Oklahoma City

State: Oklahoma Zip Code: 73154-0496 Contact Phone: (405) 767 - 4078

Lease: Harms Well #: 1-6 Sec. 6 Twp. 24 S. R. 31 East West

- C - NW Spot Location / QQQQ County: Finney

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8 Set at: 325' Cemented with: 225 Sacks

Production Casing Size: 5-1/2 Set at: 2748' Cemented with: 300 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2656-2674' Krider

Elevation: 2908 (G.L. / K.B.) T.D.: 2750 P.B.T.D.: 2625 Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): RIH to P.B.T.D., pump 25 sx cmt, plug w/200# hulls. POOH to 1500', spot 25 sx plug. POOH tbg., let cmt set up, pressure test csg to 300 psig. MIRU wireline, perf @1200', POOH, MIRU cementers, dig out bradenhead, EIR down 5-1/2" & pump 250 sx down 5-1/2" csg, tie onto 5-1/2x8-5/8 annulus, attempt to pump in. If able, pump 175 sx cmt. RDMO. Weld on cap & clean location.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Bud Neff

Phone: (620) 277 - 0803

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996 (Contractor's)

Address: P.O. Box 31, Russell, KS 67665 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 8/29/06 Authorized Operator / Agent: Altha M. Deubre-King (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202
For Jim Reisch, Asset Manager

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Chesapeake Operating, Inc.
PO Box 18496
6200 N Western Ave.
Oklahoma City, OK 73154-0496

September 01, 2006

Re: HARMS #1-6
API 15-055-00818-00-00
NW 6-24S-31W, 1320 FNL 3960 FEL
FINNEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely


David P. Williams
Production Supervisor