

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and file ONE Copy

KANSAS CORPORATION COMMISSION

API # 15 - 081-21286-00-00 (Identifier Number of this well. This must be listed for wells drilled since 1967; if no API # was issued, **RECEIVED**
AUG 30 2006

Indicate original spud or completion date 03/06/2000

Well Operator: CHESAPEAKE OPERATING, INC. CONSERVATION DIVISION
WICHITA, KS KCC License #: 32334
(Owner / Company Name) (Operator's)

Address: P. O. BOX 18496 City: OKLAHOMA CITY

State: OK Zip Code: 73154-0496 Contact Phone: (405) 848 - 8000

Lease: MLP ROONEY Well #: 4-5 Sec. 5 Twp. 30 S. R. 34 East West

SW - NW - NE Spot Location / QQQQ County: HASKELL

1250 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

2100 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8 Set at: 1855 Cemented with: 650 Sacks

Production Casing Size: 5-1/2 Set at: 5700 Cemented with: 300 Sacks

List (ALL) Perforations and Bridgeplug Sets: 5478-5631'; 5306-5510'

Elevation: 2999 (G.L. / K.B.) T.D.: 5700 PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): MIRU WOU, MIRU Cementers, dig out bradenhead, pump 300# cotton seed hulls, pump 100# CS hulls + 25 sx cmt. Pump 50 bbl mud spacer, pump 100 sx cmt, wait 30 minutes, top off with mud if necessary. Tie onto 5-1/2"x8-5/8" annulus, attempt to establish pump in. If able, pump into annulus. Pump 50 sx cmt. RDMO cementers. Weld on cap, clean up location.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Bud Neff Phone: (620) 277 - 0803

Address: 4532 W. Jones Avenue City / State: Garden City, KS 67846

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996
(Company Name) (Contractor's)

Address: P. O. Box 31, Russell, KS 67665 Phone: ()

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 8/29/06 Authorized Operator / Agent: Altha M. Devore-King
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

For Jim Reisch, Asset Manager

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Chesapeake Operating, Inc.
PO Box 18496
6200 N Western Ave.
Oklahoma City, OK 73154-0496

September 01, 2006

Re: MLP ROONEY #4-5
API 15-081-21286-00-00
SWNWNE 5-30S-34W, 1250 FNL 2100 FEL
HASKELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely



David P. Williams
Production Supervisor