

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-01530-00-00
Spot: ^{NW} SWSENE Sec/Twnshp/Rge: 14-17S-9W
3004 feet from S Section Line, 1093 feet from E Section Line
Lease Name: ROLFS Well #: 2
County: ELLSWORTH Total Vertical Depth: 3174 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3174		
SURF	12.25	240		

\$ 103.16

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2006 9:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DENNIS Company: _____ Phone: _____

Proposed Plugging Method: Casing parted at 1706'; spot cement there at salt intervals and surface through perforations.

Plugging Proposal Received By: DOUG LOUIS Witness Type: PARTIAL
Date/Time Plugging Completed: 07/24/2006 5:00 PM KCC Agent: DOUG LOUIS

Actual Plugging Report:

Fluid level at 200'. Perforated 7" casing at 1700', 1150', 850', and 290'. TIH with tubing and spotted 50 sacks of 60/40 posmix with 3% CaCl at 1700'. Let cement set for two hours. Tagged with wire line at 1300'. Spotted 35 sacks at 1150', 50 sacks at 850', and circulated cement to surface from 300' inside and outside of 7" casing.

Allied Cementing #24107
Shane's Tank Service

INVOICED
DATE 8/31/06
2007060406

Perfs: **RECEIVED
KCC DISTRICT #2
JUL 26 2006
WICHITA, KS**

Remarks:

Plugged through: TBG

**RECEIVED
AUG 30 2006
KCC WICHITA**

District: 02

Signed Day
(TECHNICIAN)