

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20251-00-01
Spot: SESESW Sec/Twnshp/Rge: 12-10S-24W
330 feet from S Section Line, 2790 feet from E Section Line
Lease Name: SE GANO UNIT Well #: 2-3
County: GRAHAM Total Vertical Depth: 4070 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		2119		\$ 132.28
PKR	2.375	3700		
PROD	4.5	4056	0	w/200 sxs cmt
SURF	8.625	190	0	w/150 sxs cmt
T1	2.375	3700		

Well Type: EOR UIC Docket No: E24173.4 Date/Time to Plug: 08/24/2006 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8104

Proposed Plugging Method: Ordered out 200 sxs Swift Multi-Density Cement with 500# hulls.
DV at 2119' w/550 sxs. Casing leaks at 3341' - 3115'; 2824' - 3082'.
Packer stuck in hole at 3740'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2006 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2200'.
Swift Services pumped 75 sxs Swift Multi Density Cement.
PTOH. Squeezed 4 1/2" casing with 125 sxs SMD with 300# hulls.
Max. P.S.I 300#. S.I.P. 100#.
Hooked up to 8 5/8" - instant pressure 500#.

Perfs:

INVOICED
DATE 8/31/06
TR. NO. 2007060471

RECEIVED
AUG 30 2006
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS BEESLEY #3. SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

AUG 28 2006

DON E. PRATT #3 BEESLEY 17-10-24W
 HAYS, KS. SE SE SW
 Contr. GARVEY DRLG. Cry. GRAHAM
 Geol. J. R. GREEN Pool GANO SE

E. 2464 KB ... Cm. 8/27/69. Cp. 10/16/69 IP PMP 182 BOPD, NW/
 LANS 3978-84

API 15-065-20,251

SMPTops	Depth	Datum
ANH	2088	+ 376
B ANH	2122	+ 342
TOP	3546	-1082
HEEB	3764	-1300
TOR	3786	-1322
LANS	3803	-1339
RTD	4070	-1606

Csg. 8-5/8" 190/150 SX
 4 1/2" 4069/200 SX
 DV TOOL 450

DST 3823-43 1/2/30", GTS/13",
 1860' OIL, NW, 18HP 1305#,
 NO FBHP, FP 69-386#

COTD, 4029; PF 3978-84, A 250
 MA; FU 1100'/15" (CGO) SWB 67
 BOPH/2 HRS, 800' OB;

NO LOG
 NO CORES

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS