

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20609-00-00
Spot: SWSNWNE Sec/Twnshp/Rge: 30-5S-19W
1072 feet from N Section Line, 1815 feet from E Section Line
Lease Name: LAPPIN Well #: 1
County: PHILLIPS Total Vertical Depth: 3750 feet

Operator License No.: 33751
Op Name: RESOURCE BUFFALO COMMONS, LLC
Address: 1894 K TERR.
STOCKTON, KS 67669

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	222		

\$ 121.88

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/18/2006 1:00 PM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: ELDO Company: RESOURCE BUFFALO COMMONS, Phone: (785) 216-0694

Proposed Plugging Method: Ordered 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 08/18/2006 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3720' w/25 sxs.
2nd. Plug at 1764' w/25 sxs.
3rd. Plug at 1079' w/100 sxs.
4th. Plug at 272' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

NOV 01 2006
DATE 8/31/06
NO. 20070-60474

RECEIVED
AUG 30 2006
KCC WICHITA

District: 04

Signed Richard Williams

(TECHNICIAN)

10/1

AUG 28 2006

RET