

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-02251-00-00
Spot: SENVNE Sec/Twnshp/Rge: 29-19S-9W
4298 feet from S Section Line, 1779 feet from E Section Line
Lease Name: S W GROVE Well #: 6
County: RICE Total Vertical Depth: 3203 feet

Operator License No.: 30364
Op Name: RESOURCE OPERATIONS, INC.
Address: BOX 9487
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	8.625	3193		250 SX
SURF	15.5	175		175 SX

\$ 104.10

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/05/2006 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/05/2006 1:00 PM KCC Agent: VIRGIL CLOTHIER

RECEIVED
KCC DISTRICT #2
JUL 27 2006
WICHITA, KS

Actual Plugging Report:

MIRU. Pulled rods and approximately 950' of rotten tubing out of the hole. Overshot tool would not go past 340'. Perforated at 800' and 260'. Ran 1" tubing down to 3040' and pumped 50 sacks of cement. Pulled 1" to 1200' and pumped 50 sacks of cement. Pulled 1" to 800' and pumped 50 sacks of cement. Pulled 1" to 260' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland #C030563

INVOICED

DATE 8/31/06
CCL NO. 20070604.75

Perfs:

RECEIVED
AUG 30 2006
KCC WICHITA

Remarks:
Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

M

AKT