

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-20076-00-00
Spot: SWNENW Sec/Twnshp/Rge: 4-16S-1W
4321 feet from S Section Line, 3746 feet from E Section Line
Lease Name: MORTIMER Well #: 5
County: SALINE Total Vertical Depth: 2665 feet

Operator License No.: 6901
Op Name: D S & W WELL SERVICING, INC.
Address: 403 FRONT STREET
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2665		125 SX
SURF	7	94		

\$ 86.61

Well Type: EOR UIC Docket No: E18390.1 Date/Time to Plug: 06/05/2006 10:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Revd. from: EDWARD S. NEMNICH Company: D S & W WELL SERVICING, INC. Phone: (620) 587-2312

Proposed Plugging Method: Sand btm to 2585' and cap w/ 4 sxs cmt. Perf @ 250' & circ cmt from 250' to surf.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 06/05/2006 2:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

100 sacks of cement was pumped through the 4-1/2" casing because the cemented 12" fiberglass tubing broke off at 65'. After shutting the well in for several hours, another 25 sacks of cement was pumped to bring the cement to the surface. 5 sacks of cement was squeezed into the backside before it locked up. Records indicated the backside was previously circulated to the surface.

130 sxs 60/40 posmix with 2% gel

Copeland Cement #30550

Perfs:

RECEIVED
KCC DISTRICT #2
JUL 3 1 2006
WICHITA, KS

INVOICE
DATE 8/31/06
NO. 2007060467

RECEIVED
AUG 3 0 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Greg Eves
(TECHNICIAN)